

**CITY OF RAPID CITY
CONSTRUCTION CHANGE ORDER**

PROJECT NAME: MINNESOTA STREET EXTENSION

PROJECT NO: ST99-605

CONTRACTOR: HEAVY CONST., INC

ORIGINAL CONTRACT AMOUNT: \$293,337.44



CHANGE ORDER NO.: 1 & FINAL

DATE: 7/12/2000

LINE ITEM	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	INSTALLED QUANTITY	INSTALLED PRICE	INCREASE/ (DECREASE)
1	Mobilization	LS	1.00	\$7,000.00	\$7,000.00	1.00	\$7,000.00	\$0.00
2	6" PVC Water Main	LF	167.00	\$13.00	\$2,171.00	206.00	\$2,678.00	\$507.00
3	12" PVC Water Main	LF	505.00	\$19.50	\$9,847.50	560.00	\$10,920.00	\$1,072.50
4	12"x12"x6" Tee	EA	3.00	\$470.00	\$1,410.00	3.00	\$1,410.00	\$0.00
5	12" 11-1/4 Bend	EA	2.00	\$315.00	\$630.00	2.00	\$630.00	\$0.00
6	12" 22-1/2 Bend	EA	1.00	\$315.00	\$315.00	1.00	\$315.00	\$0.00
7	6" Plug	EA	2.00	\$135.00	\$270.00	2.00	\$270.00	\$0.00
8	Fire Hydrant w/Aux. Valve & 6" Lead	EA	1.00	\$1,940.00	\$1,940.00	1.00	\$1,940.00	\$0.00
9	Water Main Encasement	EA	1.00	\$430.00	\$430.00	1.00	\$430.00	\$0.00
10	Tie To Existing Water Main	EA	2.00	\$450.00	\$900.00	2.00	\$900.00	\$0.00
11	Unclassified Excavation	CY	2,215.00	\$3.68	\$8,151.20	2,215.00	\$8,151.20	\$0.00
12	AASHTO T-180 Soil Test	EA	20.00	\$126.00	\$2,520.00	1.00	\$126.00	(\$2,394.00)
13	Aggregate Base Course	TON	2,775.00	\$8.71	\$24,170.25	2,793.18	\$24,328.60	\$158.35
14	Gravel Cushion	TON	115.00	\$9.00	\$1,035.00	75.69	\$681.21	(\$353.79)
15	7" PCC Pavement	SY	5,710.00	\$20.34	\$116,141.40	5,650.00	\$114,921.00	(\$1,220.40)
16	Concrete Curb & Gutter, Type B67	LF	2,850.00	\$7.00	\$19,950.00	2,850.00	\$19,950.00	\$0.00
17	Concrete Curb & Gutter, Type BL	LF	40.00	\$8.00	\$320.00	40.00	\$320.00	\$0.00
18	Concrete Sidewalk, S.F.	SF	10,097.00	\$1.80	\$18,174.60	10,097.00	\$18,174.60	\$0.00
19	Concrete Sidewalk Access Ramp	SF	313.00	\$2.15	\$672.95	313.00	\$672.95	\$0.00
20	Concrete Test Set	EA	20.00	\$94.50	\$1,890.00	5.00	\$472.50	(\$1,417.50)
21	Class M6 Concrete	CY	1.50	\$216.30	\$324.45	1.50	\$324.45	\$0.00
22	18" RCP, Class II	LF	166.00	\$25.00	\$4,150.00	166.00	\$4,150.00	\$0.00
23	24" RCP, Class II	LF	556.00	\$30.00	\$16,680.00	556.00	\$16,680.00	\$0.00
24	30" RCP, Class II	LF	76.00	\$40.00	\$3,040.00	68.00	\$2,720.00	(\$320.00)
25	30" RCP Flared End	EA	1.00	\$520.00	\$520.00	1.00	\$520.00	\$0.00
26	30" 45 Degree Bend	EA	1.00	\$950.00	\$950.00	1.00	\$950.00	\$0.00
27	Type B Inlet w/Vaned Grate	EA	8.00	\$1,060.00	\$8,480.00	8.00	\$8,480.00	\$0.00
28	Type E Inlet, 10'	EA	1.00	\$2,400.00	\$2,400.00	1.00	\$2,400.00	\$0.00
29	Edge Drain, 4" Pipe, Rock, & Fabric	LF	2,750.00	\$4.50	\$12,375.00	2,750.00	\$12,375.00	\$0.00
30	Class II RipRap w/Bedding	CY	10.00	\$34.55	\$345.50	10.00	\$345.50	\$0.00
31	Erosion Control, Silt Fence	LF	200.00	\$4.20	\$840.00	175.00	\$735.00	(\$105.00)
32	Seeding, Fertilizing, Mulching	SY	7,440.00	\$0.33	\$2,455.20	7,440.00	\$2,455.20	\$0.00
33	Cold Plastic Pvmnt Mkg, 4" Y	LF	2,218.00	\$2.21	\$4,901.78	2,330.00	\$5,149.30	\$247.52

34	Cold Plastic Pvmt Mkg, 4" Y Skip	LF	2,218.00	\$1.05	\$2,328.90	2,300.00	\$2,415.00	\$86.10
35	Cold Plastic Pvmt Mkg, 4" DY	LF	100.00	\$4.41	\$441.00	112.00	\$493.92	\$52.92
36	Cold Plastic Pvmt Mkg, 4" W	LF	50.00	\$2.21	\$110.50	50.00	\$110.50	\$0.00
37	Cold Plastic Pvmt Mkg, Arrow	EA	7.00	\$183.75	\$1,286.25	7.00	\$1,286.25	\$0.00
38	Cold Plastic Pvmt Mkg, "ONLY"	EA	1.00	\$210.00	\$210.00	1.00	\$210.00	\$0.00
39	Cold Plastic Pvmt Mkg, 24" Stop Bar	LF	52.00	\$11.55	\$600.60	48.00	\$554.40	(\$46.20)
40	Sign, "STOP"	EA	3.00	\$183.75	\$551.25	3.00	\$551.25	\$0.00
41	Contractor Staking	LS	1.00	\$7,000.00	\$7,000.00	1.00	\$7,000.00	\$0.00
42	Type 1 Bedding Material	TON	100.00	\$11.34	\$1,134.00	116.19	\$1,317.59	\$183.59
43	Insert Dowel Bars	EA	48.00	\$6.06	\$290.88	48.00	\$290.88	\$0.00
44	P.C.C. Fillets	SY	122.11	\$32.62	\$3,983.23	122.11	\$3,983.23	\$0.00
45	SIGNS	EA	0.00	\$200.00	\$0.00	13.00	\$2,600.00	\$2,600.00
46	SEEDING, REPAIR DAMAGED AREA	LS	0.00	\$450.00	\$0.00	1.00	\$450.00	\$450.00
47	HYDRANT EXTENSION, 2 FOOT	EA	0.00	\$300.00	\$0.00	1.00	\$300.00	\$300.00
48	SHOT ROCK	TON	0.00	\$12.00	\$0.00	82.90	\$994.80	\$994.80
	END BID ITEMS							
	TOTAL				\$293,337.44		\$294,133.33	\$795.89

C.C.O. HISTORY INCREASE/(DECREASE)		PRIOR ADJUSTED CONTRACT PRICE :	\$293,337.44
CCO #1	\$795.89	NET INCREASE/(DECREASE):	\$795.89
		ADJUSTED CONTRACT PRICE:	\$294,133.33
PRIOR TOTAL =	\$293,337.44	CHANGE TO DATE:	\$795.89

CONTRACTOR:		DATE:	7/12/2000
ENGINEER:		DATE:	12 JULY, 2000
MAYOR:	_____	DATE:	_____
FINANCE:	_____	DATE:	_____
CONTRACT TIME CHANGE +/-: 0		NEW CONTRACT TIME: _____ Days	

CITY OF RAPID CITY
CONSTRUCTION CHANGE ORDER

PROJECT NAME: MINNESOTA STREET EXTENSION

PROJECT NO: ST99-605

CONTRACTOR: HEAVY CONST., INC

ORIGINAL CONTRACT AMOUNT: \$293,337.44

CHANGE ORDER NO.: 1 & FINAL

DATE: 7/12/2000

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
1	Mobilization	NO CHANGE
2	6" PVC Water Main	MEASURED QUANTITY
3	12" PVC Water Main	MEASURED QUANTITY
4	12"x12"x6" Tee	NO CHANGE
5	12" 11-1/4 Bend	NO CHANGE
6	12" 22-1/2 Bend	NO CHANGE
7	6" Plug	NO CHANGE
8	Fire Hydrant w/Aux. Valve & 6" Lead	NO CHANGE
9	Water Main Encasement	NO CHANGE
10	Tie To Existing Water Main	NO CHANGE
11	Unclassified Excavation	NO CHANGE
12	AASHTO T-180 Soil Test	MEASURED QUANTITY
13	Aggregate Base Course	MEASURED QUANTITY
14	Gravel Cushion	MEASURED QUANTITY
15	7" PCC Pavement	MEASURED QUANTITY
16	Concrete Curb & Gutter, Type B67	NO CHANGE
17	Concrete Curb & Gutter, Type BL	NO CHANGE
18	Concrete Sidewalk, S.F.	NO CHANGE
19	Concrete Sidewalk Access Ramp	NO CHANGE
20	Concrete Test Set	NO CHANGE
21	Class M6 Concrete	MEASURED QUANTITY
22	18" RCP, Class II	NO CHANGE
23	24" RCP, Class II	NO CHANGE

24	30" RCP, Class II	MEASURED QUANTITY
25	30" RCP Flared End	NO CHANGE
26	30" 45 Degree Bend	NO CHANGE
27	Type B Inlet w/Vaned Grate	NO CHANGE
28	Type E Inlet, 10'	NO CHANGE
29	Edge Drain, 4" Pipe, Rock, & Fabric	NO CHANGE
30	Class II RipRap w/Bedding	NO CHANGE
31	Erosion Control, Silt Fence	MEASURED QUANTITY
32	Seeding, Fertilizing, Mulching	NO CHANGE
33	Cold Plastic Pvmnt Mkg, 4" Y	MEASURED QUANTITY
34	Cold Plastic Pvmnt Mkg, 4" Y Skip	MEASURED QUANTITY
35	Cold Plastic Pvmnt Mkg, 4" DY	MEASURED QUANTITY
36	Cold Plastic Pvmnt Mkg, 4" W	NO CHANGE
37	Cold Plastic Pvmnt Mkg, Arrow	NO CHANGE
38	Cold Plastic Pvmnt Mkg, "ONLY"	NO CHANGE
39	Cold Plastic Pvmnt Mkg, 24" Stop Bar	MEASURED QUANTITY
40	Sign, "STOP"	NO CHANGE
41	Contractor Staking	NO CHANGE
42	Type 1 Bedding Material	MEASURED QUANTITY
43	Insert Dowel Bars	NO CHANGE
44	P.C.C. Fillets	NO CHANGE
45	SIGNS	NEW ITEM ADDED TO CLOSE MAPLE AND WISCONSIN UNTILL WALGAR COMPLETES THEM
46	SEEDING, REPAIR DAMAGED AREA	NEW ITEM TO REPAIR SEEDING DAMAGED BY OFFROADERS
47	HYDRANT EXTENSION, 2 FOOT	NEW ITEM TO RAISE HYDRANT LEFT IN DEPRESSION BY WALGAR
48	SHOT ROCK	NEW ITEM TO STABILIZE TRENCH

PREPARED BY: JOE JAGODZINSKI

DATE: 12 JULY, 2000