

PW081501-04

PROJECT NO: IDP00-1008

ORIGINAL CONTRACT AMOUNT:	\$1,509,000.00
----------------------------------	-----------------------

DATE: July 31, 2001

LINE ITEM	SEC NO	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	INSTALLED QUANTITY	INSTALLED PRICE	INCREASE/ (DECREASE)
1	NA	Provide roof Ladder to Little Boy's Gym	1	1	\$1,086.40	\$1,086.40			\$1,086.40
2	NA	Ceiling mounted receptacle in shop room, relocate switch	1	1	\$1,096.96	\$1,096.96			\$1,096.96
3	NA	Relocate exist. Building sign and plaques	1	1	\$537.76	\$537.76			\$537.76
4	NA	Oak veneer plywood cover at demo'ed opening	1	1	\$226.46	\$226.46			\$226.46
5	NA	One hour fire assembly above existing wall	1	1	\$725.38	\$725.38			\$725.38
6	NA	Delete ACT in rooms 134 & 132	1	1	(\$1,697.85)	(\$1,697.85)			(\$1,697.85)
7	NA	Add flashing extension at canopy	1	1	\$525.81	\$525.81			\$525.81
8	NA	Exist water softner/relocate reconnect	1	1	\$834.13	\$834.13			\$834.13
9	NA	Combustion air duct in mech. Room	1	1	\$836.52	\$836.52			\$836.52
10	NA	GFI receptacle in shower room	1	1	\$60.98	\$60.98			\$60.98
11	NA	Sump pump receptacle move/ water softner receptacle	1	1	\$98.42	\$98.42			\$98.42
12	NA	120V connection to water heater	1	1	\$48.78	\$48.78			\$48.78
13	NA	Refeed hall 130, de-energized by demo	1	1	\$243.93	\$243.93			\$243.93
14	NA	Remove underfloor connections exposed during wall demo	1	1	\$1,651.25	\$1,651.25			\$1,651.25
15	NA	Install type "b" fixture in vest. 133	1	1	\$210.13	\$210.13			\$210.13
16	NA	Provide circuit breaker at outlet near hood	1	1	\$139.28	\$139.28			\$139.28
17	NA	Provide 120V relay in make up air, interlock dishwasher to RTU	1	1	\$215.17	\$215.17			\$215.17
18	NA	Eliminate Elec. Gas valve/ volume control in kitchen	1	1	(\$72.32)	(\$72.32)			(\$72.32)
19	NA	Replace duct/smoke detector at supply duct uncovered at demo	1	1	\$839.12	\$839.12			\$839.12
20	NA	Change branch circuit to CUH-1	1	1	\$343.80	\$343.80			\$343.80
21	NA	Add deadbolt to door 132	1	1	\$273.42	\$273.42			\$273.42
22	NA	Install new door in Main gym at old freezer opeing	1	1	\$1,174.19	\$1,174.19			\$1,174.19
23	NA	Delete conc. infill in j.c. 135, add ships ladder and rail	1	1	\$168.74	\$168.74			\$168.74
24	NA	Door 116 switch changed to keyed switch	1	1	\$89.35	\$89.35			\$89.35
25	NA	Change toaster plug ends	1	1	\$82.74	\$82.74			\$82.74
26	NA	Add cord and ends to hot well	1	1	\$76.65	\$76.65			\$76.65
27	NA	Change receptacle for microwave	1	1	\$54.66	\$54.66			\$54.66
28	NA	Demo of underfloor conduit in Dave's office	1	1	\$581.70	\$581.70			\$581.70
		TOTAL				\$10,451.56			\$10,451.56

C.C.O. HISTORY INCREASE/(DECREASE)		PRIOR ADJUSTED CONTRACT PRICE :	\$1,553,311.84
CCO #1	\$8,804.95	NET INCREASE/(DECREASE):	\$10,451.56
CCO #2	\$11,731.72		
CCO #3	\$23,775.17	ADJUSTED CONTRACT PRICE:	\$1,563,763.40
PRIOR TOTAL	\$44,311.84	CHANGE TO DATE: (3.6% change)	\$54,763.40

CONTRACTOR:	_____	DATE:	_____
ARCHITECT:	_____	DATE:	_____
MAYOR:	_____	DATE:	_____
FINANCE:	_____	DATE:	_____
CONTRACT TIME CHANGE +/-: 0 NEW CONTRACT TIME: Per Original Contract			

CITY OF RAPID CITY
CONSTRUCTION CHANGE ORDER

PW081501-04

Rapid City Club for Boys, Inc., Expansion 2000

PROJECT NO: IDP00-1008

Heavy Constructors, dba Gustafson Builders

ORIGINAL CONTRACT AMOUNT: \$1,509,000.00

CHANGE ORDER NO.: 4

DATE: July 31, 2001

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
1	Provide roof Ladder to Little Boy's Gym	Value added request by the owner
2	Ceiling mounted receptacle in shop room, relocate switch	Value added request by the owner
3	Relocate exist. Building sign and plaques	Value added request by the owner
4	Oak veneer plywood cover at demo'ed opening	After demolition, opening required additional treatment
5	One hour fire assembly above existing wall	Part of an existing wall did not meet requirements to become a new 1hr. Rated corridor
6	Delete ACT in rooms 134 & 132	Requested by the owner, ACT to go in at a later date
7	Add flashing extension at canopy	Hide from view the white strip of PVC roofing around the canopy
8	Exist water softner/relocate reconnect	Existence of water softner was missed in original design
9	Combustion air duct in mech. Room	Combustion air duct was missing in original design
10	GFI receptacle in shower room	Additional receptacle in shower room
11	Sump pump receptacle move/water softner receptacle	Sump pump moved so sump pump receptacle had to move, water softner was tied into same.
12	120V connection to water heater	change connection to water heater
13	Refeed hall 130, de-energized by demo	Demolition cut electricity to outlets in hall 130
14	Remove underfloor connections exposed during wall demo	Demolition exposed connections which had to be re-routed
15	Install type "b" fixture in vest. 133	No outlet called for in original design
16	Provide circuit breaker at outlet near hood	Hood moved over close enough to outlet to warrant a circuit breaker
17	Provide 120V relay in make up air, interlock dishwasher to RTU	provide correct connections
18	Eliminate Elec. Gas valve/ volume control in kitchen	Owner request
19	Replace duct/smoke detector at supply duct uncovered at demo	Additional supply duct uncovered required an additional duct/smoke detector
20	Change branch circuit to CUH-1	Cabinet Unit Heater moved to outside wall
21	Add deadbolt to door 132	Value added request by the owner
22	Install new door in Main gym at old freezer opeing	Value added request by the owner
23	Delete conc. infill in j.c. 135, add ships ladder and rail	Value added request by the owner
24	Door 116 switch changed to keyed switch	Owner request
25	Change toaster plug ends	Equipment arrived different that scheduled
26	Add cord and ends to hot well	Equipment arrived different that scheduled
27	Change receptacle for microwave	Equipment arrived different that scheduled
28	Demo of underfloor conduit in Dave's office	Electrical connections uncovered during demo had to be rerouted

PREPARED BY Dan Coon

DATE: