CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER

PW010202-04

PROJECT NAME: DEADWOOD AVENUE EROSION CONTROL PROJECT

PROJECT NO:

SSD00-1022

CONTRACTOR: MORRIS CONSTRUCTION CO.

ORIGINAL CONTRACT AMOUNT:

\$11,075.00

CHANGE ORDER NO.: 1F


DATE:


20-Dec-01

LINE ITEM	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE		INSTALLED QUANTITY	INSTALLED PRICE	INCREASE/ (DECREASE)
1	MOBILIZATION	LS	1	\$1,000.00	\$1,000.00	1	\$1,000.00	\$0.00
2	CLEARING & GRUBBING	LS	1	\$1,000.00	\$1,000.00	1	\$1,000.00	\$0.00
3	BORROW, IMPORTED (NORTH SITE)	CY	335	\$3.00	\$1,005.00	335	\$1,005.00	\$0.00
4	BORROW, IMPORTED (SOUTH SITE)	CY	240	\$8.00	\$1,920.00	504	\$4,032.00	\$2,112.00
5	TOPSOIL, FURNISH & PLACE	SY	200	\$10.00	\$2,000.00	396	\$3,960.00	\$1,960.00
6	EROSION CONTROL, HI-VELOCITY EXCELSIOR BLANKET	SY	875	\$2.00	\$1,750.00	1597	\$3,194.00	\$1,444.00
7	SEEDING & FERTILIZING	SY	1800	\$0.50	\$900.00	2414	\$1,207.00	\$307.00
8	INCIDENTAL WORK	LS	1	\$1,500.00	\$1,500.00	1	\$1,500.00	\$0.00
	Additional Items							
9	SEED, FERTILIZER, MULCH	SY	0	\$0.70	\$0.00	2000	\$1,400.00	\$1,400.00
10	REPAIR ROCK & WIRE BASKETS SOUTHSITE 5/21/01	LS	0	\$388.13	\$0.00	1	\$388.13	\$388.13
11	REGRADE DITCH/CHECK DAMS/SOUTHSITE 5/31-6/2, 2001	LS	0	\$2,453.02	\$0.00	1	\$2,453.02	\$2,453.02
12	PLACE SECOND, CHECK DAMS, REGRADE - SOUTHSITE	LS	0	\$3,711.03	\$0.00	1	\$3,711.03	\$3,711.03
13	REMOVE FABRIC, LOWER GRADE, DIG OUT 2ND DRAIN	LS	0	\$8,402.44	\$0.00	1	\$8,402.44	\$8,402.44
14	REGRADE NORTHSITE BORROW AREA 10/30 - 10/31, 2001	LS	0	\$180.00	\$0.00	1	\$180.00	\$180.00
	TOTAL	-		 	\$11,075.00		\$33,432.62	\$22,357.62

C.C.O. HISTORY INCREASE/(DECREASE) PRIOR ADJUSTED CONTRACT PRICE \$11,075.00 CCO #1 \$22,357.62 NET INCREASE/(DECREASE): \$22,357.62 CCO#2 CCO #3 ADJUSTED CONTRACT PRICE: \$33,432.62 PRIOR TOTAL = CHANGE TO DATE: \$22,357.62 CONTRACTOR: DATE: 12-2101 ENGINEER: 12.21.61 DATE: MAYOR: DATE: FINANCE: DATE: CONTRACT TIME CHANGE +/-: 0 NEW CONTRACT TIME: Days

CITY OF RAPID CITY





PROJECT NAME:	DEADWOOD	AVENUE EROSION	CONTROL	PROJECT

PROJECT NO:

SSD00-1022

CONTRACTOR: MORRIS CONSTRUCTION CO.

ORIGINAL CONTRACT AMOUNT:

\$11,075.00

CHANGE	ORDER	NO.	1 F
CHANGE	OKDEK	110	TT.

DATE:

20-Dec-01

		DITE. 20-DCC-01
ITEM	DESCRIPTION	REASON FOR CHANGE
4	BORROW, IMPORTED (SOUTH SITE), CY	(INCREASE 264.0 CY) DUE TO REGRADING OF DRAINAGE DITCH, ORIGINAL WASHED AWAY FROM HEAVY RAINFALL, RUNOFF - FOUND HIDDEN DRAIN PIPE NEARBY THAT ADDED TO RUNOFF. SEE ATTACHMENTS.
5	TOPSOIL, FURNISH & PLACE, CY	(INCREASE 196.0 CY) SAME REASON AS ITEM #4
6	EROSION CONTROL, HI-VELOCITY EXCELSIOR BLANKET, SY	(INCREASE 722.0 SY) DUE TO LOSS AT SOUTHSITE REASONS PER ITEM #4. PLACED ADDITIONAL BLANKET AT NORTHSITE ON BORROW SITE THAT STARTED ERODING . SEE ATTACHMENTS.
7	SEEDING & FERTILIZING, SY	(INCREASE 614.0 SY) DUE TO REASONS FOR ITEM #6 - NORTHSITE.
9	SEED, FERTILIZER, MULCH, SY	(INCREASE 2000.0 SY) ADDED ITEM DUE TO HAVING TO RE-SEED SOUTHSITE REASONS PER ITEM #4.
10	REPAIR ROCK & WIRE BASKETS SOUTHSITE 5/21/01	(INCREASE 1.0 EACH) ADDED ITEM DUE TO HEAVY RUNOFF PER ITEM #4.
11	REGRADE DITCH/CHECK DAMS/SOUTHSITE 5/31-6/2, 2001	(INCREASE 1.0 EACH) ADDED ITEM - REASONS PER ITEM #4
12		(INCREASE 1.0 EACH) ADDED ITEM - REASONS PER ITEM #4
13	REMOVE FABRIC, LOWER GRADE, DIG OUT 2ND DRAIN PIPE, RIPRAP - SOUTHSITE 6/23 - 7/17, 2001	(INCREASE 1.0 EACH) ADDED ITEM - REASONS PER ITEM #4
14	REGRADE NORTHSITE BORROW AREA 10/30 - 10/31, 2001	(INCREASE 1.0 EACH) ADDED ITEM - SEE ITEM #6 - NORTHSITE
	<i>y y</i>	

PREPARED BY:	Loren e.	Chileberry.	DATE:	12. 21.01
	· · · · /			