

**CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER NO. # 1 AND FINAL
RED ROCK CANYON DRAINAGE IMPROVEMENTS
DR01-960
JULY 12, 2001
ORIGINAL CONTRACT AMOUNT: \$200,419.20
CONTRACTOR: RCS CONSTRUCTION, INC.**

LINE ITEM	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	INSTALLED QUANTITY	INSTALLED PRICE	INCREASE/ (DECREASE)	
BID ALTERNATIVE NUMBER 1									
1	INCIDENTAL WORK	LS	1	\$800.00	\$800.00	1.00	\$800.00	\$0.00	
2	MOBILIZATION	LS	1	\$15,000.00	\$15,000.00	1.00	\$15,000.00	\$0.00	
3	CLEARING & GRUBBING, 18" + TREES	EA	5	\$80.00	\$400.00	5.00	\$400.00	\$0.00	
4	CLEARING & GRUBBING	LS	1	\$250.00	\$250.00	1.00	\$250.00	\$0.00	
5	WATER MAIN ENCASEMENT	LF	55	\$6.10	\$335.50	0.00	\$0.00	(\$335.50)	
6	WATER MAIN LOWERING	EA	1	\$910.00	\$910.00	0.00	\$0.00	(\$910.00)	
7	PIPELINE INSULATION	SF	220	\$6.55	\$1,441.00	0.00	\$0.00	(\$1,441.00)	
8	EXCAVATION, UNCLASSIFIED	CY	1,230	\$5.55	\$6,826.50	1,230.00	\$6,826.50	\$0.00	
9	AASHTO T-180 SOIL TEST	EA	1	\$275.00	\$275.00	0.00	\$0.00	(\$275.00)	
10	TOPSOIL, FURNISH & PLACE	CY	100	\$8.55	\$855.00	0.00	\$0.00	(\$855.00)	
11	TOPSOIL, STOCKPILE & REPLACE	CY	75	\$5.50	\$412.50	75.00	\$412.50	\$0.00	
12	SAWING, ASPHALT PAVEMENT	LF	94	\$1.65	\$155.10	94.00	\$155.10	\$0.00	
13	REMOVE & DISPOSE ASPHALT PAVEMENT	SY	278	\$2.25	\$625.50	440.00	\$990.00	\$364.50	
14	REMOVE & DISPOSE CONCRETE CURB &	LF	268	\$4.00	\$1,072.00	315.50	\$1,262.00	\$190.00	
15	REMOVE & RESET WOOD FENCE	LF	15	\$63.50	\$952.50	0.00	\$0.00	(\$952.50)	
16	REMOVE CONCRETE BOX CULVERT	LS	1	\$3,200.00	\$3,200.00	1.00	\$3,200.00	\$0.00	
17	REMOVE & DISPOSE CONCRETE	SF	125	\$1.50	\$187.50	290.00	\$435.00	\$247.50	
18	AGGREGATE BASE COURSE	T	50	\$14.00	\$700.00	194.00	\$2,716.00	\$2,016.00	
19	ASPHALT CONCRETE, CLASS G, TYPE 1	T	63	\$51.00	\$3,213.00	77.91	\$3,973.41	\$760.41	
20	ASPHALT CONCRETE, CLASS G, TYPE 2	T	35	\$53.00	\$1,855.00	76.60	\$4,059.80	\$2,204.80	
21	CONCRETE CURB & GUTTER, TYPE B66	LF	172	\$14.00	\$2,408.00	335.50	\$4,697.00	\$2,289.00	
22	CONCRETE SIDEWALK, 4"	SF	725	\$3.60	\$2,610.00	792.50	\$2,853.00	\$243.00	
23	CONCRETE TEST SET	EA	3	\$104.00	\$312.00	2.00	\$208.00	(\$104.00)	
24	12" CSP SLOTTED DRAIN, 14 GA.	LF	40	\$75.00	\$3,000.00	40.00	\$3,000.00	\$0.00	
25	FLOWABLE FILL FOR APRONS	CY	50.0	\$51.00	\$2,550.00	50.00	\$2,550.00	\$0.00	
26	PRECAST CONC. BOX, 12' X 6'	LF	150	\$518.00	\$77,700.00	144.00	\$74,592.00	(\$3,108.00)	
27	PRECAST CONC. BOX END SECTIONS, 12' X	EA	6	\$5,323.00	\$31,938.00	6.00	\$31,938.00	\$0.00	
28	DITCH & CHANNEL PROT. BASKETS	CY	321	\$98.00	\$31,458.00	321.00	\$31,458.00	\$0.00	
29	EROSION CONTROL, HI-VELOCITY	SY	270	\$3.05	\$823.50	252.00	\$768.60	(\$54.90)	
30	SEEDING, FERTILIZING, MULCHING	SY	2,250	\$0.50	\$1,125.00	2,850.00	\$1,425.00	\$300.00	
31	SODDING	SY	13.9	\$4.00	\$55.60	120.00	\$480.00	\$424.40	
32	6' CHAIN LINK FENCE, COMPL.	LF	112	\$28.00	\$3,136.00	112.00	\$3,136.00	\$0.00	
33	TRAFFIC CONTROL	LS	1	\$3,300.00	\$3,300.00	1.00	\$3,300.00	\$0.00	
34	FLAGGING	HR	60.00	\$17.00	\$1,020.00	17.00	\$289.00	(\$731.00)	
35	STRIP DRAIN EXTENSION	LS	0.00	\$1,815.24	\$0.00	1	\$1,815.24	\$1,815.24	
TOTAL							\$200,902.20	\$202,990.15	\$2,087.95

CCO #1&F

NET INCREASE/(DECREASE):

\$2,087.95

ADJUSTED CONTRACT PRICE:

\$202,990.15

PRIOR TOTAL =

CHANGE TO DATE:

\$2,087.95

CONTRACTOR: _____

DATE: _____

ENGINEER: _____

DATE: 22 MAY 2002

JOE JAGODZINSKI, PE

MAYOR: _____

DATE: _____

FINANCE: _____

DATE: _____

CONTRACT TIME CHANGE +/-: 0

NEW CONTRACT TIME: Days

**CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER NO.1 & FINAL
RED ROCK CANYON DRAINAGE IMPROVEMENTS**

DR01-960

JULY 12, 2001

ORIGINAL CONTRACT AMOUNT: \$200,419.20

CONTRACTOR: RCS CONSTRUCTION, INC.

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
1	INCIDENTAL WORK	NO CHANGE
2	MOBILIZATION	NO CHANGE
3	CLEARING & GRUBBING, 18" + TREES	NO CHANGE
4	CLEARING & GRUBBING	NO CHANGE
5	WATER MAIN ENCASEMENT	NONE NEEDED
6	WATER MAIN LOWERING	NONE NEEDED
7	PIPELINE INSULATION	NONE NEEDED
8	EXCAVATION, UNCLASSIFIED	NO CHANGE
9	AASHTO T-180 SOIL TEST	NONE NEEDED
10	TOPSOIL, FURNISH & PLACE	NONE NEEDED
11	TOPSOIL, STOCKPILE & REPLACE	NO CHANGE
12	SAWING, ASPHALT PAVEMENT	NO CHANGE
13	REMOVE & DISPOSE ASPHALT PAVEMENT	MEASURED QUANTITY
14	REMOVE & DISPOSE CONCRETE CURB & GUTTER	MEASURED QUANTITY
15	REMOVE & RESET WOOD FENCE	NONE NEEDED
16	REMOVE CONCRETE BOX CULVERT	NO CHANGE
17	REMOVE & DISPOSE CONCRETE SIDEWALK	MEASURED QUANTITY
18	AGGREGATE BASE COURSE	MEASURED QUANTITY
19	ASPHALT CONCRETE, CLASS G, TYPE 1	EXTENDED STREET DUE TO EXISTING WATER SEWER ENCASEMENT & GRADE CHANGE
20	ASPHALT CONCRETE, CLASS G, TYPE 2	EXTENDED STREET DUE TO EXISTING WATER SEWER ENCASEMENT & GRADE CHANGE
21	CONCRETE CURB & GUTTER, TYPE B66	EXTENDED STREET DUE TO EXISTING WATER SEWER ENCASEMENT & GRADE CHANGE
22	CONCRETE SIDEWALK, 4"	MEASURED QUANTITY
23	CONCRETE TEST SET	MEASURED QUANTITY
24	12" CSP SLOTTED DRAIN, 14 GA.	NO CHANGE
25	FLOWABLE FILL FOR APRONS	NO CHANGE
26	PRECAST CONC. BOX, 12' X 6'	DELIVERED LENGTH - MEASURED QUANTITY
27	PRECAST CONC. BOX END SECTIONS, 12' X 6'	NO CHANGE
28	DITCH & CHANNEL PROT. BASKETS	NO CHANGE
29	EROSION CONTROL, HI-VELOCITY EXCELSIOR BLANKET	MEASURED QUANTITY
30	SEEDING, FERTILIZING, MULCHING	MEASURED QUANTITY
31	SODDING	MEASURED QUANTITY
32	6' CHAIN LINK FENCE, COMPL.	NO CHANGE
33	TRAFFIC CONTROL	NO CHANGE
34	FLAGGING	MEASURED QUANTITY
35	STRIP DRAIN EXTENSION	EXTENDED STREET DUE TO EXISTING WATER SEWER ENCASEMENT & GRADE CHANGE

22-May-02