CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER NO. 1 44TH STREET RECONSTRUCTION, W. MAIN TO W. SOUTH STREET ST02-938

FEBRUARY 28, 2002

ORIGINAL CONTRACT AMOUNT: \$592,728.25 CONTRACTOR: HILLS MATERIALS COMPANY

LINE			CONTRACT	UNIT	EXTENDED	INSTALLED	INSTALLED	BALANCE
ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE	PRICE	QUANTITY	PRICE	REMAINING
1	MOBILIZATION	LS	1.00	\$3,200.00	\$3,200.00		\$0.00	incomplete
2	CLEARING & GRUBBING, 6" +TREE	EA	39.00	\$100.00	\$3,900.00		\$0.00	incomplete
3	CLEARING & GRUBBING	LS	1.00	\$750.00	\$750.00		\$0.00	incomplete
4	STANDARD MANHOLE, 48" DIA.	EA	1.00	\$1,675.00	\$1,675.00		\$0.00	incomplete
5	ADJUST MANHOLE RING & COVER	EA	2.00	\$700.00	\$1,400.00		\$0.00	incomplete
6	FIRE HYDRANT EXTENSION, 18"	EA	1.00	\$370.00	\$370.00		\$0.00	incomplete
7	ADJUST VALVE BOX	EA	11.00	\$90.00	\$990.00		\$0.00	incomplete
8	TYPE I GRANULAR BACKFILL	Т	200.00	\$13.00	\$2,600.00		\$0.00	incomplete
9	TYPE II GRANULAR BACKFILL	Т	200.00	\$12.00	\$2,400.00		\$0.00	incomplete
10	INCIDENTAL WORK	LS	1.00	\$4,150.00	\$4,150.00		\$0.00	incomplete
11	EXCAVATION, UNCLASSIFIED	CY	8,400.00	\$5.20	\$43,680.00	8575	\$44,590.00	\$910.00
12	AASHTO T-180 SOIL TEST	EA	12.00	\$140.00	\$1,680.00		\$0.00	incomplete
13	TOPSOIL, PLACE	CY	1,550.00	\$4.20	\$6,510.00		\$0.00	incomplete
14	TOPSOIL, SALVAGE	CY	1,550.00	\$2.30	\$3,565.00		\$0.00	incomplete
15	MILL & REMOVE ASPHALT CONCRETE PAVEMENT, FULL DEPTH REMOVE CONCRETE DRIVEWAT	SY	18,484.00	\$0.95	\$17,559.80		\$0.00	incomplete
16	DAVEMENT	SY	73.00	\$3.00	\$219.00		\$0.00	incomplete
17	REMOVE CONCRETE CURB AND GUTTER	LF	1,400.00	\$1.10	\$1,540.00		\$0.00	incomplete
18	REMOVE CONCRETE FILLET & PAN	SY	16.00	\$7.00	\$112.00		\$0.00	incomplete
19	REMOVE CONCRETE GUTTER PAN	SF	24.00	\$2.00	\$48.00		\$0.00	incomplete
20	REMOVE CONCRETE SIDEWALK	SY	9.00	\$4.00	\$36.00		\$0.00	incomplete
21	REMOVE INLET BOX	EA	3.00	\$175.00	\$525.00		\$0.00	incomplete
22	REMOVE PIPE CULVERT	LF	229.00	\$6.15	\$1,408.35		\$0.00	incomplete
23	REMOVE GUARD RAIL	LF	357.00	\$3.60	\$1,285.20		\$0.00	incomplete
24	PLACING COLD MILLED ASPHALT	CY	1,800.00	\$7.10	\$12,780.00		\$0.00	incomplete
	AGGREGATE BASE COURSE	Т	2,400.00	\$10.00	\$24,000.00		\$0.00	incomplete
26	AGGREGATE BASE COURSE-OVER SOIL SUPPORT FABRIC	Т	800.00	\$11.00	\$8,800.00	1600	\$17,600.00	\$8,800.00
27	SOIL SUPPORT FABRIC/GEOGRID	SY	2,400.00	\$2.60	\$6,240.00	4800	\$12,480.00	\$6,240.00
28	GRAVEL SURFACING	Т	12.00	\$11.00	\$132.00		\$0.00	
29	ASPHALT CONCRETE, CLASS G, TYPE 1	Т	3,412.00	\$30.00	\$102,360.00		\$0.00	
30	ASPHALT CONCRETE, CLASS G, TYPE 2	Т	1,678.00	\$31.40	\$52,689.20		\$0.00	
31	CONCRETE APPROACH PAVEMENT, 6"	SY	185.00	\$42.00	\$7,770.00		\$0.00	
32	CONCRETE DRIVEWAY PAVEMENT, 6"	SY	34.00	\$42.00	\$1,428.00		\$0.00	
33	CONCRETE "P6" GUTTER	LF	324.00	\$10.00	\$3,240.00		\$0.00	
34	CONCRETE CURB & GUTTER, TYPE B66	LF	4,285.00	\$12.00	\$51,420.00		\$0.00	
35	CONCRETE FILLET & PAIN (REINFORCED),	SY	115.00	\$58.00	\$6,670.00		\$0.00	
36	CONCRETE SIDEWALK, 4"	SF	22,880.00	\$2.90	\$66,352.00		\$0.00	

No. PW062602-02

37	24" SLOTTED DRAIN 14 GA.	LF	77.00	\$105.00	\$8,085.00		\$0.00	
38	15" RCP, CLASS III	LF	160.00	\$42.50	\$6,800.00		\$0.00	
39	18" RCP, CLASS III	LF	310.00	\$30.50	\$9,455.00		\$0.00	
40	36" RCP, CLASS II	LF	6.00	\$350.00	\$2,100.00		\$0.00	
41	15" RCP FLARED END	EA	3.00	\$410.00	\$1,230.00		\$0.00	
42	48" RCP FLARED END W/ TRASH GUARD	EA	1.00	\$2,550.00	\$2,550.00		\$0.00	
43	48" X 48" RCP TEE	EA	1.00	\$1,200.00	\$1,200.00		\$0.00	
44	48" RCP CAP	EA	1.00	\$325.00	\$325.00		\$0.00	
45	48" X 36" RCP REDUCER	EA	1.00	\$365.00	\$365.00		\$0.00	
46	SPECIAL TYPE "B" INLET W/VANED GRATE	EA	1.00	\$2,700.00	\$2,700.00		\$0.00	
47	TYPE "B" INLET W/CURBED COVER	EA	6.00	\$2,100.00	\$12,600.00		\$0.00	
48	TYPE "E" INLET, 5'	EA	3.00	\$4,400.00	\$13,200.00		\$0.00	
49	12" EDGE DRAIN & ROCK	LF	3,900.00	\$4.60	\$17,940.00		\$0.00	
50	DITCH & CHANNEL PROT. BASKETS	CY	18.00	\$200.00	\$3,600.00		\$0.00	
51	EROSION CONTROL, HAY BALES	EA	30.00	\$11.00	\$330.00		\$0.00	
52	EROSION CONTROL, SILT FENCE	LF	2,000.00	\$3.00	\$6,000.00		\$0.00	
53	SEEDING, FERTILIZING, MULCHING,	ACRE	3.00	\$2,000.00	\$6,000.00		\$0.00	
54	PAVEMENT MARKING PAINT, 4" WHITE	LF	5,327.00	\$0.20	\$1,065.40		\$0.00	
55	PAVEMENT MARKING PAINT, 4" YELLOW	LF	10,254.00	\$0.20	\$2,050.80		\$0.00	
56	COLD PLAST. MARKING, 8"	LF	998.00	\$6.25	\$6,237.50		\$0.00	
57	COLD PLAST. MARKING, 24"	LF	99.00	\$20.00	\$1,980.00		\$0.00	
58	COLD PLAST. MARKING, ARROW	EA	10.00	\$220.00	\$2,200.00		\$0.00	
59	COLD PLAST. MARKING, MESSAGE	WORD	3.00	\$220.00	\$660.00		\$0.00	
60	CONSTRUCTION STAKING	LS	1.00	\$17,000.00	\$17,000.00		\$0.00	
61	REGULATORY SIGNS	EA	14.00	\$155.00	\$2,170.00		\$0.00	
62	STREET SIGNS	EA	8.00	\$110.00	\$880.00		\$0.00	
63	FLEXIBLE DELINEATOR POSTS	EA	10.00	\$46.00	\$460.00		\$0.00	
64	TRAFFIC CONTROL	LS	1.00	\$10,500.00	\$10,500.00		\$0.00	
65	CONCRETE TEST SET	EA	8.00	\$150.00	\$1,200.00		\$0.00	
66	WATER LINE ENCASEMENT	EA	2.00	\$680.00	\$1,360.00		\$0.00	
67	FLAGGING	HR	400.00	\$17.50	\$7,000.00		\$0.00	
	Change Order #1							
68	SOUTH	LS	0.00	\$16,303.57	\$0.00	1	\$16,303.57	\$16,303.57
69	GABION ROCK	Т	0.00	\$22.40	\$0.00	200	\$4,480.00	\$4,480.00
	TOTAL				\$592,728.25		\$95,453.57	\$36,733.57

No. PW062602-02

C.C.O. HISTORY INCREASE/(DECREASE)	PRIOR ADJUSTED CONTRACT PRICE :	\$592,728.25
CCO #1	\$36,733.57 NET INCREASE/(DECREASE):	\$36,733.57
CCO #2 CCO #3	ADJUSTED CONTRACT PRICE:	\$629,461.82
PRIOR TOTAL =	CHANGE TO DATE:	\$36,733.57
CONTRACTOR:	DATE:	
ENGINEER:	DATE:14 June	ક, 2002
MAYOR:	DATE:	
FINANCE:	DATE:	
CONTRACT TIME CHANGE +/-: 7 NEW CONTRACT TIM	E: 127 Days	

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER NO. 1 44TH STREET RECONSTRUCTION, W. MAIN TO W. SOUTH STREET ST02-938

FEBRUARY 28, 2002

ORIGINAL CONTRACT AMOUNT: \$592,728.25 CONTRACTOR: HILLS MATERIALS COMPANY

LINE		
ITEM	DESCRIPTION	REASON FOR CHANGE
11	EXCAVATION, UNCLASSIFIED	INCREASED DUE TO SOFT SUBGRADE TREATED BY EXTRA EXCAVATION, GEOGRID AND EXTRA BASCOU
26	AGGREGATE BASE COURSE-OVER SOIL SU	INCREASED DUE TO SOFT SUBGRADE TREATED BY EXTRA EXCAVATION, GEOGRID AND EXTRA BASCOU
27	SOIL SUPPORT FABRIC/GEOGRID	INCREASED DUE TO SOFT SUBGRADE TREATED BY EXTRA EXCAVATION, GEOGRID AND EXTRA BASCOU
68	WATER MAIN STUB AT RAIDER ROAD SOUT	ADDED TO BETTER SERVICE AREA TO EAST/ESTABLISH LOOPED CONNECTION
69	GABION ROCK	NEW ITEM TO ADDRESS SMALL EXTRA SOFT SUBGRADE AREAS NOT REPAIRABLE WITH GEOGRID

PREPARED BY:	DATE: 19 JUNE, 2002
JOE JAGODZINSKI PE	

JOE JAGODZINSKI, PE PROJECT MANAGER