

## REQUEST FOR ADVERTISING AUTHORITY

This form must be completed and approved by the City Finance Office prior to presenting items to the City Council and/or Committees of the City Council. This covers all items which require formal bids, currently anything over \$25,000 (except emergency and repair costs)

I. PROJECT NO.: MIP11-1923 CIP No. 50298  
 II. PROJECT NAME: 2011 MISCELLANEOUS IMPROVEMENTS PROJECT  
 III. Project/Item(s) Description: ANNUAL IMPROVEMENTS AT VARIOUS LOCATIONS INCLUDING ADA RAMPS CURB & GUTTER AND ASPHALT ALLEY REPAIR.

IV. BID LETTING DATE: April 21, 2011

V. ESTIMATED COST OF PROJECT/ITEM(S) \$ 100,000.00



VI. BASIS OF PAYMENT Assessed  Non-Assessed   
 Single Payment  Partial Payment  XXX

VII. APPROPRIATION DATA

Amount	100,000			
Fund Name	MIP			
Department	4370			
Line Item	8913			
Fund	505			

VIII. (If applicable) Grant No.: \_\_\_\_\_  
 Funding Source: CIP  
 Estimated Completion Date: JULY 1ST, 2011  
 Estimated Grant Receipt Date: \_\_\_\_\_

IX. DEPARTMENT/DIVISION:

Project Manager: PAUL FAIMAN Date 3/9/2011  
 Date 4-11-11  
 DIVISION MANAGER Signature  
 Date 4-11-11  
 DEPARTMENT DIRECTOR Signature

FINANCE OFFICE USE ONLY			Approved		Carbon Copy
Appropriation Cash Flow	Date	Initial	Yes		Investment Desk Public Works Engineering Project Manager

This will be a Partial Payment/Non - Assessed Project. Payments will be made once each month as the work progresses and per the Standard Specifications Section 7.59.

**SITE SPECIFIC DETAILS  
SITES  
INCLUDED IN  
MISCELLANEOUS IMPROVEMENTS  
PROJECT MIP11-1923**

**NOTE: The site number corresponds with numbers found on the various site location maps.**

SITE NUMBER	WORK COMMENTS/REQUIREMENTS
1.	<b>ALLEY FROM ST. FRANCIS TO ST. ANNE, 7<sup>TH</sup> TO MT. RUSHMORE. RD:</b> Mill existing asphalt (2" depth) to create inverted crown. Place 2" asphalt overlay. Remove existing curb & gutter and approach pavement, replace with new reinforced curb & gutter and reinforced approach per standard detail.
2.	<b>ALLEY FROM FRANKLIN TO ST. CHARLES, MT. RUSHMORE RD. TO 7<sup>TH</sup> STREET:</b> Mill existing asphalt (3" depth) to create inverted crown. Place 3" asphalt overlay. Remove and replace reinforced concrete approach and sidewalk. If a traffic control is necessary on Mt. Rushmore Road, the contractor must coordinate with the Rapid City Area D.O.T. Engineers office.
3.	<b>QUINCY STREET @ 11<sup>TH</sup> INTERSECTION:</b> Remove asphalt pavement as marked in the field. Install reinforced concrete pan and fillets. Remove and replace additional curb & gutter adjacent to fillets. This work does not require the installation of ADA ramps due to existing sidewalk locations in this neighborhood.
4.	<b>WILLOWBEND ROAD EAST OF MARLIN DRIVE:</b> Remove asphalt pavement as marked in the field. Repair subgrade by digout and replacement of base course as needed. Replace asphalt pavement per city specifications.
5.	<b>3201 WILLOWBEND ROAD:</b> Remove sidewalk as marked in the field. Adjust existing manhole (frame & grate supplied by utility maintenance). Install sidewalk after manhole adjusted to correct grade. Return existing frame & grate to the Rapid City Utility Maintenance division.
6.	<b>1201 &amp; 1202 RACINE STREET:</b> Remove and replace sidewalk that is holding water, as marked in the field. Confirm the final installation of sidewalk will drain properly.
7.	<b>WEST OMAHA BETWEEN 38<sup>TH</sup> STREET AND NORDBY LANE:</b> Remove asphalt pavement as marked and construct reinforced concrete pan. Remove and replace additional curb & gutter and construct fillets per attached detailed drawing. Install new sidewalk with ADA access ramp at the location shown, per City of Rapid City standard plate 61-5.

8.	<b>WESTRIDGE ROAD, PARK DRIVE TO MEADOWBROOK DRIVE:</b> Remove & replace sidewalk and curb & gutter damaged by previous utility work. Removal limits marked in the field.
9.	<b>SHERIDAN LAKE ROAD MEDIAN ISLAND:</b> Remove sidewalk damaged by previous utility work. Replace sidewalk as indicated in the field.

**Note:** Any new construction that receives vandalism or damage will be replaced at the contractor's expense. **PROTECT YOUR WORK.**

# 2011 MIP Overall Vicinity Map

