11. INCIDENTAL WORK

Included in the bid item 'Incidental Work, Lump Sum', but not necessarily limited to are; any permit fees, saw cuts needed to accomplish the work, cushion material for sidewalks, six inch sidewalk curb for ADA ramps, adjustments to lawn sprinkler systems, disposal of excess excavation, rock, concrete and asphalt removals; expansion joints, concrete drilling, hand seeding, reinforcing steel, or any other items referred to as 'Incidental Work' in the Standard Specifications and/or these Detailed Specifications. Plastic concrete testing will be required per the City of Rapid City standard specifications and will be considered incidental to their respective bid items. The contractor is encouraged to coordinate concrete placements to best utilize the plastic concrete testing.

12. COMPLETION TIME

The project completion date is fixed at August 24, 2012.

Work started at one site shall continue steadily until it is completed.

13. PROJECT PAYMENT

This will be a Partial Payment/Non - Assessed Project. Payments will be made once each month as the work progresses and per the Standard Specifications Section 7.59.

SITE SPECIFIC DETAILS SITES INCLUDED IN MISCELLANEOUS IMPROVEMENTS PROJECT MIP12-2004

NOTE: The site number corresponds with numbers found on the various site location maps.

SITE NUMBER	WORK COMMENTS/REQUIREMENTS
1.	HAINES AVENUE INLET SIDEWALK REPAIR: Remove and replace 4" non-reinforce concrete sidewalk adjacent to Type 'E' drop inlets at various locations.
2.	PLANT STREET CURB AND STREET REPAIR: Remove & replace damaged curb & gutter at several locations as indicated in the field. Saw & remove asphalt pavement adjacent to curb repairs. Place base course and asphalt pavement per City of Rapid City Standard Specifications.
3.	EAST SAINT PATRICK STREET & SOUTH VALLEY DRIVE INTERSECTION: Install ADA ramps with property line sidewalk compliant with City of Rapid City Specifications.
4.	HOMESTEAD STREET SIDEWALK INSTALLATION: Install 4' property line sidewalk between property owners.

DS-5

4.	HOMESTEAD STREET SIDEWALK INSTALLATION: Install 4' property line sidewalk between property owners.
5.	FIFTH STREET & TEXAS STREET SIGNAL UPGDRADE: Install ADA accessible sidewalk ramps in conjunction with signalized intersection. Adjustment of a water service curb box and an electrical J-Box will be required and considered incidental.
6.	ALLEY @ 3 RD STREET FROM MEADE STREET TO INDIANA: Remove and replace 6" reinforced sidewalk and install 6" reinforced driveway approach.
7.	Remove reinforced driveway approach and re-construct.
8.	ALLEY @ CLARK STREET BETWEEN 11 TH & 12 TH STREET: Remove & replace sidewalk and install reinforced driveway approach to correct drainage from alley onto sidewalk.
9.	PARK DRIVE CURB & GUTTER AND STREET REPAIR: Remove curb & gutter damaged by previous utility work. Replace curb & gutter and asphalt patch.
10.	SOUTH CANYON ROAD: Install ADA accessible sidewalk ramps including cross walks.
11.	CARMEL POINT DRAINAGE: Remove & replace drain pan to improve relief from sidewalk drain.
12.	44 th STREET CURB AND STREET REPAIR: Saw and remove damaged curb & gutter and asphalt. Place base course to grade and place asphalt patch.
13.	MAIN STREET WEST OF FIFTH STREET INTERSECTION: Remove curb & gutter and sidewalk necessary to install a 5' ADA curb ramp. Install sidewalk curb and handrail.
14.	MINNEWASTA AREA DRAINAGE UPGRADES: Install 4" thick, 6' wide drain pan with invert to alleviate and control drainage issues. Gabion baskets will be installed at the downstream end of the drain pan. The area will be excavated and a base course foundation installed and compacted to provide a solid level pad.
15.	FLORMAN STREET DRAINAGE: Remove driveway pan and install Type 'D' curb and gutter.

Note: Any new construction that receives vandalism or damage will be replaced at the contractor's expense. **PROTECT YOUR WORK.**

