

BID AWARD SUMMARY

LETTING DATE: September 9, 2014

PROJECT: Pavement Rehabilitation Project – 1st and 2nd Street
Project No. 14-2204 / CIP No. 50844

RECOMMENDATION: City staff recommends all bids for this project be rejected at the September 15, 2014 Council Meeting and authorize staff to re-advertise for bids.

City Staff has evaluated the bid for this project and has determined that it is not in the best interest of the City to award this project at this time. City Staff recommends re-bidding this project at a later date with modifications to the project schedule.

BIDDERS' SUMMARY

CONTRACTORS

TOTAL BID


Hills Materials	\$433,814.25
-----------------	--------------

FUNDING SOURCE	TOTAL	Streets	Drainage	Water
ADVERTISING AUTHORITY	\$285,000.00	\$200,000	\$50,000	\$35,000
ENGINEER'S ESTIMATE	\$343,000.00			


APPROPRIATION DATA:

FUNDING SOURCE	TOTAL	Streets	Drainage	Water
COST CENTER		8910	8911	933
LINE ITEM		4370	4371	4381
FUNDING CENTER		505	505	602
BID AMOUNT	\$433,814.25	\$280,941.50	\$104,000.00	\$48,872.75

PROJECT MANAGER:


Todd Peckosh, PE
City of Rapid City

DATE:



PROJECT NAME: Pavement Rehabilitation Project - 1st and 2nd Street

PROJECT NUMBER: PROJECT NO. 14-2204 / CIP NO. 50844

LET DATE: September 9, 2014

LOW BID AMOUNT: \$433,814.25


ITEM NO.	STD. BID ITEM NO.	DESCRIPTION OF ITEM	UNIT	QTY (EST)	ENGINEER'S ESTIMATE		HILLS MATERIALS COMPANY	
					UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
1		Mobilization	LS	1	\$12,000.00	\$12,000.00	\$15,000.00	\$15,000.00
2		Construction Staking	LS	1	\$6,000.00	\$6,000.00	\$7,500.00	\$7,500.00
3		Traffic Control	LS	1	\$7,700.00	\$7,700.00	\$10,500.00	\$10,500.00
4		Incidental Work	LS	1	\$14,221.58	\$14,221.58	\$11,500.00	\$11,500.00
5		Construction Fencing	LF	1,450	\$3.50	\$5,075.00	\$11.85	\$17,182.50
6		Remove Concrete Curb and Gutter	LF	477	\$13.50	\$6,439.50	\$13.00	\$6,201.00
7		Remove Concrete Pavement	SY	135	\$20.00	\$2,700.00	\$22.50	\$3,037.50
8		Remove Storm Sewer Main	LF	523	\$13.03	\$6,814.69	\$18.00	\$9,414.00
9		Remove Water Main	LF	12	\$9.00	\$108.00	\$20.00	\$240.00
10		Remove & Replace Inlet Throat	EA	1	\$800.00	\$800.00	\$2,100.00	\$2,100.00

11		Remove Manhole	EA	1	\$1,100.00	\$1,100.00	\$715.00	\$715.00
12		Remove Asphalt Pavement	SY	2,634	\$4.25	\$11,194.50	\$7.00	\$18,438.00
13		AASHTO T180 Soil Test	EA	2	\$175.00	\$350.00	\$325.00	\$650.00
14		Excavation, Unclassified	CY	878	\$30.00	\$26,340.00	\$41.00	\$35,998.00
15		Placing Topsoil	CY	8	\$21.00	\$168.00	\$160.00	\$1,280.00
16		Gravel Surfacing, Temporary	Ton	101	\$25.50	\$2,575.50	\$33.70	\$3,403.70
17		3/4" Base Course	Ton	916	\$28.00	\$25,648.00	\$31.15	\$28,533.40
18		Base Course, Salvaged	CY	234	\$14.00	\$3,276.00	\$51.00	\$11,934.00
19		Adjust Manhole Ring & Cover	EA	2	\$673.30	\$1,346.60	\$860.00	\$1,720.00
20		Connect to Existing Water Main	EA	2	\$1,467.30	\$2,934.60	\$4,475.00	\$8,950.00
21		Connect to Existing Storm Sewer	EA	4	\$915.00	\$3,660.00	\$960.00	\$3,840.00
22		18" RCP Class 2	LF	264	\$47.38	\$12,508.32	\$82.50	\$21,780.00
23		24" RCP Class 2	LF	260	\$65.00	\$16,900.00	\$91.50	\$23,790.00
24		60" Manhole	EA	1	\$4,700.00	\$4,700.00	\$7,100.00	\$7,100.00
25		8" Water Main	LF	265	\$37.90	\$10,043.50	\$61.00	\$16,165.00
26		8" 45 Degree Bend	EA	4	\$630.00	\$2,520.00	\$1,000.00	\$4,000.00
27		Type B69 Concrete Curb and Gutter	LF	37	\$30.00	\$1,110.00	\$68.00	\$2,516.00

28	Type B66 Concrete Curb and Gutter	LF	392	\$25.50	\$9,996.00	\$40.00	\$15,680.00
29	6" Concrete P-Gutter	LF	48	\$21.75	\$1,044.00	\$30.00	\$1,440.00
30	9" Non-Reinforced PCC Pavement	SY	135	\$73.16	\$9,876.60	\$140.00	\$18,900.00
31	Install #10 Steel Bar in Concrete	EA	80	\$20.00	\$1,600.00	\$25.00	\$2,000.00
32	Asphalt Concrete Composite	Ton	901	\$115.00	\$103,615.00	\$100.00	\$90,100.00
33	6" Non-Reinforced Approach Pavement	SY	27	\$60.00	\$1,620.00	\$135.00	\$3,645.00
34	4" Pavement Marking - Paint	LF	1,375	\$0.60	\$825.00	\$0.60	\$825.00
35	4" Groove for Pavement Marking	LF	1,554	\$0.84	\$1,305.36	\$0.85	\$1,320.90
36	4" Cold Applied Plastic Pavement Marking	LF	1,554	\$3.50	\$5,439.00	\$3.50	\$5,439.00
37	12" Groove for Pavement Marking	LF	315	\$3.25	\$1,023.75	\$5.00	\$1,575.00
38	12" Cold Applied Plastic Pavement Marking	LF	315	\$8.00	\$2,520.00	\$12.50	\$3,937.50
39	24" Groove for Pavement Marking	LF	180	\$5.00	\$900.00	\$10.00	\$1,800.00
40	24" Cold Applied Plastic Pavement Marking	LF	180	\$13.50	\$2,430.00	\$27.00	\$4,860.00
41	Groove for Cold Applied Plastic Pavement Marking	SF	55	\$3.00	\$165.00	\$5.00	\$275.00
42	Cold Applied Plastic Pavement Marking	SF	55	\$13.50	\$742.50	\$7.50	\$412.50
43	Pedestrian Crossing Sign and Post	EA	4	\$205.00	\$820.00	\$600.00	\$2,400.00
44	Sodding	SY	39	\$15.00	\$585.00	\$20.00	\$780.00

45		Seeding Fertilizing and Mulching	SY	91	\$10.00	\$910.00	\$3.75	\$341.25
46		Rock Construction Entrance	Ton	36	\$195.00	\$7,020.00	\$50.00	\$1,800.00
47		Erosion Control, Inlet Protection	EA	4	\$150.00	\$600.00	\$200.00	\$800.00
48		Erosion Control, Gravel Filled Filter Bag	LF	266	\$6.50	\$1,729.00	\$7.50	\$1,995.00
TOTAL						\$343,000.00		\$433,814.25

I certify that, to the best of my knowledge, this is a true tabulation of bids received for this project.


 Todd Peckosh, PE
 Project Manager

9/10/14
 Date