

## SCOPE OF SERVICES:

### Task A - Boundary and Trailhead Surveys

Perform boundary survey for selected locations at Skyline Wilderness Park. Recover and mark property corners. Prepare drawing showing found and marked monuments. Provide preliminary staking at proposed trailhead locations. Monument new Skyline right-of-way for utility company relocation.

### Task B - Flormann Street Sewer Extension

Investigate feasibility of gravity sewer extension to Stonewall restroom site in lieu of sewer holding tank. Prepare technical memo with schematic design and cost estimates. Perform supplemental topographic and boundary survey on Flormann Street for sewer extension. Prepare final design and plans for 560 feet of 8-inch gravity sewer main in Skyline Drive and Flormann Street. Prepare final design of gravity sewer service from new sewer main to Stonewall site restroom.

### Task C - Trailhead Redesigns at W. Dinosaur and Stonewall Sites

Investigate alternative grading designs to accommodate proposed recreational trail alignments. Prepare conceptual grading alterations. Prepare final grading and site development designs. Adjust and modify related plans to accommodate new grading and improvements.

### Task D - Supplemental Plan Submittal


Incorporate recommended plans revisions from Public Works Department after final plan submittal. Modify bidding quantities and add bid alternates. Print modified final plans and make additional final plans submittal.

### Task E - Plans and Specifications Alteration to Add Insulation to Stonewall Restroom

Modify plans and specifications to include ceiling and wall insulation in prefabricated restroom. (ARC International).

### Task F - Supplemental Services for Task 5 – Expanded Construction Services

Add daily on-site construction observations services (Task 5.5) to 80% of full-time on-site observation services for an anticipated 6-month construction period (mid-April – October 2015).

  
Greg Wijrenga, P.E.  
Project Manager

Date: 2-4-15