Customer: First Presbyterian Church

Bob James Office

Project Name:

710 Kansas City Street First

Presbyterian Church

Quote Number: 597114

Line # Location:

21

Attributes

Viewed From Exterior
Rough Opening: 82--1/4" X 59--3/4"

Impervia, 3-Wide Casement, 81.75 X 59.25, Tan

1: Non-Standard Size Left Casement Frame Size: 19 1/2 X 59 1/4

General Information: Standard, Duracast, Block Frame (3-1/4"), Foam Insulated

Exterior Color / Finish: Tan Interior Color / Finish: Tan Interior

Glass: Insulated Low E SunDefense Argon Gas

Hardware Options: Standard, Standard Roto Operator, Color Matched

Screen: Full Screen

Grille: GBG, No, 3/4" Contour, Traditional (2W5H)

Vertical Mull 1: FactoryMull, Standard (Vertical Factory) (0")

2: Non-Standard Size Fixed Casement

Frame Size: 42 3/4 X 59 1/4

General Information: Standard, Duracast, Block Frame (3-1/4"), Foam Insulated

Exterior Color / Finish: Tan Interior Color / Finish: Tan Interior

Glass: Insulated Low E SunDefense Argon Gas Grille: GBG, No, 3/4" Contour, Traditional (4W5H) Vertical Mull 2: FactoryMull, Standard (Vertical Factory) (0")

3: Non-Standard Size Fixed Casement

Frame Size: 19 1/2 X 59 1/4

General Information: Standard, Duracast, Block Frame (3-1/4"), Foam Insulated

Exterior Color / Finish: Tan Interior Color / Finish: Tan Interior

Glass: Insulated Low E SunDefense Argon Gas Grille: GBG, No, 3/4" Contour, Traditional (2W5H)

Wrapping Information: Perimeter Length = 282", Glazing Pressure = 50.