


Interior Material Finish Schedule

(The color schedules in the drawings indicate the initial color selections for the project. Because the potential for product substitutions & discontinuation of colors, final color selections will be made by the architect after all color submittals have been received from the contractor.)

TYPE	Finishes	
	ITEM	COLOR
WOOD DOORS	NEW WOOD DOOR TO MATCH EXISTING VANBACH'S DOORS	
CEILING	SAG-1	REPLACE EXISTING SAG W/ NEW 'TINY' CEILING IN EXISTING GRID, PAINT GRID TO MATCH CEILING PANELS
FLOORING	EXISTING ENGINEERED WOOD	EXISTING FLOOR TO BE DISTRESSED AND "WHITE-WASHED" - VERIFY W/ ARCH SAMPLE
BASE	WD	WOOD BASE TO MATCH EXISTING VANBACH'S CASING, PT-2
PAINT	PT-1	BENJAMIN MOORE, NATURAL CREAM OC-14, FINISH TO MATCH VANBACH'S
	PT-2 (casings & trim)	BENJAMIN MOORE, NATURAL CREAM OC-14, GLOSS
	PT-3 (accent wall)	TBD, VERIFY WITH TENANT & ARCH
	PT-4 (brick wall)	TBD, VERIFY WITH TENANT & ARCH

1 Second Floor Enlarged Plan
A2.0 Scale 1/4" = 1'-0"



Eric Monroe Architecture, LLC
605.787.0710
814 West Blvd.
Rapid City, SD 57701
eric@ericmonroearchitecture.com



512 Main Street
Second Floor Renovation
Suite 240
Rapid City, SD 57701

revisions

date
09/09/13

A2.0