






Existing - 4/1 = 8 total

- (1) Primary façade (north)
- (5) East façade
- (2) West façade



Proposed – (6) Pella Pro-Line Aluminum Clad –wood finished inside (purchased) & (2) Crestline windows (alum-wood, Vinyl, or wood-wood)



Existing - Group Windows 3/1 sides and 5/1 center = 2 total

- (1) Primary façade
- (1) West façade



Proposed – Grouped double hung pocket windows by Crestline in alum-wood, vinyl, or wood-wood



**South Façade

(2) Existing double hung vinyl windows and (1) 4/1 window; not requesting to be changed with 14RS021



**Note: Existing Brick Moulding can be retained for replacement Crestline Pocket Alum-Wood windows



** East Façade

(1) Existing double hung window not requesting to be replaced