

Post 320 Indoor Training Facility

Proposed relocations

- Electrical
- Water
- Sewer *
- Telephone

New Restroom

* Existing sewer to be removed and replaced with Schedule 40 PVC per code to serve new facility. Sewer to be sleeved under footing and cleanouts installed on both sides of facility. Rerouting of existing sewer is not feasible and installation of new sewer line will meet new construction installation requirements.