Golden West
TECHNOLOGIES & INTERNET SOLUTIONS
2727 N Plaza Dr.
Rapid City, SD 57702
Phone 605-348-6529 Fax 605-342-1160

Quote

No. **37451**
Date: 2/29/2012

Prepared for:
Gerri Johnston (605) 415-8295
Rapid City, City of
300 Sixth Street
Rapid City, SD 57701 U.S.A.

Prepared by: Jerry M. Gyles
Account No.: 1209
Phone: (605)394-4142

JOB: CSAC TO LIBRARY

Qty.	Description
1200.00	4 STRAND S/M ARMORED CABLE
8	3M Single Mode Hot Melt Connectors
2	Leviton 3pk Fiber optic plate w/SC Conn
2.00	PANDUIT SC 3 PACK FAP3WEDSC
2	Leviton 0-12 port rack mount empty, blk
2	S/M 3 Meter LC/SC Duplex
1.00	MISC. PULLING APPRT. CONDUIT, FITTINGS
1.00	MISC. FIBER EXPENDABLES
1	17 inch X 30 Quazite ground vault
1	Communications Cover
8.00	FUSION SPLICING & SPLICE CASES
1.00	TRENCHING & CONDUIT EXCAVATING SPECIALISTS
1.00	LABOR-CABLING-REG
1.00	MISC. FREIGHT, HANDLING & APPLICABLE TAXES

Item Total:	$26,931.19
Tax at 0.000%:	$0.00
Total:	**$26,931.19**

Prices are firm until 5/31/2012

Quoted by: Jerry M. Gyles, jerrygyles@goldenwest.com Date: 2/29/2012

Golden West Technologies in conjunction with Excavating Specialist will install at the edge of the sidewalk at the northwest corner of the CSAC building one ground vault, and from there to the man hole we will install one 2" inter duct. We will install in this inter duct one four strand SM fiber optic cable to the main rack, install a rack mount fiber box, and terminate with SC hot melt connectors. We will at the ground vault fusion splice four fibers. to the existing fiber optic cable. At other end we will install one 2" inter duct from the hand hole on the west side of 5th street south to the alley and over to the northeast corner of the Library. At this location we will penetrate the building, install a junction box and install conduit from that point to the penetration point getting us into the false ceiling. We will from the hand hole to the main rack in the Library install a four strand SM fiber optic cable, install a rack mount fiber box and terminate with SC hot melt connectors. At the hand hole we will fusion splice four fibers and install splice case. We will remove and replace the concrete, at the corner of the Library and the alley south of Kansas City street. All fibers will be tested to meet or exceed TIA/EIA standards. Installation will meet or exceed all State, Local and National codes. All work will be completed by BICSI trained and certified technicians. Our technicians are also certified Fire stop installers. Any additions beyond this scope of work will be completed on a time and material bases after your approval.

2727 N Plaza Dr.
Rapid City, SD 57702
Phone 605-348-6529 Fax 605-342-1160

Quote

No. **37451**

Date: 2/29/2012

Prepared for:
Gerri Johnston (605) 415-8295
Rapid City, City of
300 Sixth Street
Rapid City, SD 57701 U.S.A.

Prepared by: Jerry M. Gyles
Account No.: 1209
Phone: (605)394-4142

JOB: CSAC TO LIBRARY

Qty.	Description

Accepted by: _____ Date: _____

Unless otherwise specified, all labor is charged on a time and materials basis. Any additional service charge or travel will apply.
Terms: 30% down payment required for sales of $ 5,000.00 or more, with the balance due Net 15 days of invoicing.
A 40% fee may be added to any account that is sent to collections due to failure to pay.