

02SR029



NOTE: DEMOLITION DENOTES LIMITS OF EXCAVATION. CONTRACTOR TO DETERMINE EXCAVATION, EMBANKMENT, RETAINAGE METHODS (I.E. SHEETPILE, ETC.)

DEMOLITION NOTES:

- ▲ SAW-CUT ASPHALT AS NECESSARY TO ACCOMMODATE THE PIPE LENGTH NEEDED. (110'-0" FROM BACK OF KANSAS CITY ST. CURB.
- ▲ DEMOLISH AND DISPOSE OF PAVING, (ASPHALT AND CONCRETE)
- ▲ DEMOLISH AND DISPOSE OF CURBS & GUTTER TO JOINT
- ▲ REMOVE, BREAK ANY EMBEDMENT CONCRETE OFF POSTS AND SALVAGE POSTS/STIONS TO CITY STREETS DEPARTMENT.
- ▲ REMOVE AND SALVAGE TO PENNINGTON COUNTY BUILDING AND GROUNDS.
- ▲ DEMOLISH AND DISPOSE OF BRICK PAVING. DEMOLISH AND DISPOSE OF SIDEWALK TO BACK OF KANSAS CITY ST. CURB.
- ▲ STABILIZE AND MAINTAIN FOUNDATION, BRICK KNEE-WALL AND RAMPS.
- ▲ REMOVE TREE. (COORDINATE WITH PENNINGTON COUNTY BUILDING AND GROUNDS)
- ▲ DEMOLISH AND DISPOSE OF SIDEWALK, STEPS AND BRICK EDGING TO CUT-LINE.
- ▲ SAW-CUT AS NECESSARY TO ACCOMMODATE THE PIPE DEPTH NEEDED. DEMOLISH AND DISPOSE OF PAVING, (ASPHALT AND CONCRETE)
- ▲ MOVE AND RELOCATE TREE AS PER MIKE PETERSON'S DIRECTION.
- ▲ DEMOLISH AND DISPOSE OF CURBS. SAW-CUT AS NEEDED, OR REMOVE FROM CONSTRUCTION JOINT TO CONSTRUCTION JOINT.
- ▲ SUPPORT AND MAINTAIN WATER SERVICE LINES

