



CITY OF RAPID CITY

Engineering Services

300 Sixth Street

Rapid City, SD 57701-2724

Telephone: 605-394-4154 Fax: 605-394-6636

May 6, 2009

To: Growth Management Dept.

From: Todd Peckosh, PE
Project Engineer

Re: 44th Street Reconstruction
Project # ST05-1435 / CIP No. 50365

This memo is to provide information on the scope of work proposed under the referenced project.

The project will include the following elements (please refer to the submitted drawings):

- Reconstruct 44th Street from Ridgewood Street to approximately 250 feet north of West Main Street and reconstruct West Main Street from approximately 100 feet west of 44th Street to South Canyon Road. The typical section will include 36 feet of pavement; sidewalks on the west side of 44th and north side of W. Main; bike paths (per bike path plan) along the east side of 44th and south side of W. Main and gabion wall for grading needed for the bike path along West Main Street.
- Reconstruct all sanitary sewer with 8" PVC primarily located in the center of the streets.
- Reconstruct all water main with 10" PVC in 44th Street south of West Main Street and with 14" PVC in West Main Street and in 44th Street north of West Main Street.
- Reconstruct the existing twin 48" culverts with a double 9'x8' box culvert, and other storm sewer improvements.

Also attached for your information are the legal descriptions of adjacent properties.

Please let me know if there are any questions or additional information is needed.



EQUAL HOUSING
OPPORTUNITY

EQUAL OPPORTUNITY EMPLOYER