



Reinforcing Schedule:
 #4 rebar-18" on ctrs.- each way
 6" Reinforced PCC Pavement
 (see specs below)
 over 6" Granular Base Course
 Provide Fine broomed finish
 parallel to east-west block
 layout (as shown)

The shaded area shown shall be made
 in one continuous pour on a poly
 vapor barrier using a Komponent Type
 K additive with a mix design of:

Type I/II Cement	517 lbs.
Komponent Type K Additive	94 lbs.
ASTM C33 Concrete Sand	1182 lbs.
1" Concrete Rock Size 57	1444 lbs.
3/8" clean chips	340 lbs.
Water	33.7 gallons
Air	281 lbs.
	5.5% ± 1.5%

The slab shall be constantly water cured
 for seven days using Summer Cure
 blanket(s) by Midwest Canvas Corporation.

PRELIMINARY

Fisk Land Surveying
 & Consulting, Inc.
 1001 1st Avenue, Suite 200
 Rapid City, SD 57701
 (605) 343-4400
 Fax: (605) 343-4401
 Email: info@fiskland.com
 Web: www.fiskland.com

Paving Plan
 Founders Plaza
 Rapid City
 Pennington County, South Dakota

Surveyed by	Mike H.
Drawn by	Mike H.
Checked by	Mike H.
Reviewed by	Mike H.
Approved by	Mike H.
Project No.	09SR056
Sheet No.	1 of 1
Scale	As Shown
Notes	