

09SR085

Statement of Work – SDN Communications, Butler CAT Facilities

Installation of a new fiber optic cable to service the Butler CAT facilities. Cable is a new service. Cable to be placed in the public right-of-way along the west side of North Deadwood Ave approximately 30 feet from the centerline. Cable to be placed approximately 42" deep in right-of-way. One cable consisting of 48 fibers as well as one vacant 1.25" PVC duct will be placed in the bore. Construction consists of directional boring cable. Placement of two handholds with fiber warning signs located near Tatanka Drive and 70' feet north of the Butler CAT access driveway (Drawings attached)

Cable then swings west at the handhold 70' north of the Butler CAT access driveway and follows the east side of the Butler CAT access driveway to the Butler CAT building. Cable will be placed approximately 42" deep. One cable consisting of 12 fibers, one vacant 1.25" PVC duct and tracer wire will be placed via directional bore.

RECEIVED

SEP 17 2009

**Rapid City Growth
Management Department**