



FTC Express TRANSIT SHELTER

- REMOVE 7' X 12' AREA OF ASPHALT PAVEMENT
- CONSTRUCT STANDARD SHELTER FOUNDATION (MATCH EXISTING ASPHALT AT DOORWAY)
- PATCH ASPHALT AROUND FOUNDATION
- INSTALL TRANSIT SHELTER

RECEIVED

OCT 15 2009

Rapid City Growth
Management Department