


11UR011



- 1 2004 METER SOCKET, FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR
- (2) 100A NEMA 3R FUSED DISCONNECT, FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR
- 3 2" CONDUIT, FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR FROM DISCONNECT TO BIS POWER CABINET W/ (3) 2 AWG CU & (1) 6 AWG CU.
- 4 2 AWG SOUD TINNED BOW TO GROUND RING THRU 3/4" FLEX CONDUIT SEALED WITH SILICONE 12" AGL BONDED TO DISCONNECT
- (5) ELECTRIC: 2" PVC SERVICE ENTRANCE FROM DEMARCATION w/ (3) 2 AWG CU, w/ PULL STRING, CAP DO NOT GLUE; DO NOT ROUTE CONDUIT UNDER CONCRETE PAD
- 6) 2 AWG SOLID TINNED BCW TO GROUND RING THRU 3/4" FLEX CONDUIT SEALED WITH SULCONE 12" AGL BONDED TO TELCO GROUND BAR
- 7 2" CONDUIT FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR FROM TELCO CABINET TO BTS
- TELCO: 2" PVC SERVICE ENTRANCE FROM DEMARCATION POINT BY CIVIL CONTRACTOR, W/ PULL STRING, CAP DO NOT GLUE; DO NOT ROUTE CONDUIT UNDER CONCRETE PAD
- 9 12" CONCRETE PIER W/ 3"-0" DEPTH MIN (TYP. 2)

1 H-FRAME DETAIL

و PROJECT NO: 01-08-686 CHECKED BY: BOH FIRE STATION COLO SELF-SUPPORT TOWER 1930 PROMISE ROAD RAPID DITY, SD POMENCTON COUNTY SELF-SUPPORT TOWER H-FRAME DETAILS

