



PROJECT PLANT SCHEDULE

SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QUANTITY
TREES				
ACAS2	ACER SACCHARINUM 'SILVER QUEEN'	SILVER QUEEN MAPLE	2" CAL MN	3
GT8	QUERCUS MOENCHANTHOS 'BURBANK'	BURBANK HONEYLOCUST	1-1/2" CAL MN	7
JUN	JUGLANS NIGRA	BLACK WALNUT	1-1/2" CAL MN	4
MALPF	MALLUS PYRAEAFRIFE	PRAIRIEPIRE GRABAPPLE	1-1/2" CALIPER	2
PRD	PRUNUS POCOEROSA	PONDEROSA PINE	8T. HT.	8
SHRUBS				
AGAB	AMELANCHIER Q. AUTUMN BRILLIANCE (CLUMP)	SERVICEBERRY	3 GAL	
ABG	BURNING BURLUNDY CAROLINE	BURNING BURLUNDY CAROLINE, BARBERSY	3 GAL	
BMW	BURLES MICROPHYLLIA WINTERGREEN	WINTERGREEN BOXWOOD	1 GAL	
CATT	COTONEASTER ADPRESSUS TOM THUMB	CREEPING COTONEASTER	3 GAL	
CL	COTONEASTER LUCIDA	HEDGE COTONEASTER	3 GAL	
EPB	EUONYMUS FORTUNEI 'SLONDY'	PURPLELEAF EUONYMUS	3 GAL	
FIG	FORSYTHIA 'NORTHERN GOLD'	NORTHERN GOLD	3 GAL	
LMH	LONICERA X NYCTAGINACEAE 'MINILOBE'	GLOBE HONEYBUCKLE	3 GAL	
J98	JUNIPERUS SABINA 'BUFFALO'	BUFFALO JUNIPER	3 GAL	
SJP	SPIREA JAPONICA 'LITTLE PRINCESS'	LITTLE PRINCESS SPIREA	3 GAL	
VINES				
CB8	CLEMATIS SCANDENS 'BALLARIN'	AMERICAN REVOLUTION BITTERROOT	1 GAL	
CR	CLEMATIS 'RHAPSODY'	CLEMATIS	1 GAL	
HLMH	HUMULUS LUPULUS 'MT. HOOD'	MT. HOOD HOPS	1 GAL	
H	PERENNIALS			
BN	SALVIA NEMEROSA SP	DAYLILY - TALL	1 GAL	
		MAY NIGHT SALVIA	QUARTS	

POINT CALCULATIONS

1.1	SITE AREA	38,588
1.2	BUILDING AREA	7,711
1.3	POINTS REQUIRED	14,797
	POINTS PROVIDED	
	7 LARGE TREES	14,000
	7 MEDIUM TREES	7,000
	1 MEDIUM EVERGREEN	1,000
	2 SMALL TREES	1,000
	GROUNDCOVER	
	SHRUBS	
	6,837 SF GRASS	7,587
	TOTAL POINTS	30,000

\*LANDSCAPE POINTS REQUIRED PER CITY LANDSCAPE ORDINANCE

PLANTING NOTES:

- GENERAL PLANTING REQUIREMENTS
- SEE DETAIL SHEET FOR LANDSCAPE AND PLANTING DETAILS & SEE PROJECT MANUAL FOR LANDSCAPE SPECIFICATIONS
  - THE LOCATIONS OF EXISTING UTILITIES SHOWN ON THE PLANS ARE BASED ON THE BEST AVAILABLE INFORMATION. SOURCE OF BASE SHEETS IS PROJECT ARCHITECT'S AND ENGINEER. THE LANDSCAPE ARCHITECT ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS INFORMATION OR THE UNOVERTY OMISSION OF ANY SUCH INFORMATION. THE INSTALLER SHALL CALL UNDERGROUND SERVICE ALERT (U.S.A.) AT (800)227-2800 AT LEAST 48 HOURS PRIOR TO ANY EXCAVATION FOR MARKOUTS OF EXISTING UNDERGROUND FACILITIES
  - THE INSTALLER SHALL BE RESPONSIBLE FOR ANY DAMAGES TO ANY UTILITIES CAUSED BY HIS/HER PROJECT OPERATIONS
  - THE INSTALLER SHALL MAINTAIN REASONABLE ACCESS TO ALL PRIVATE DRIVEWAYS, PARKING AREAS AND AREAS THAT REQUIRE PUBLIC ACCESS DURING CONSTRUCTION
  - VERIFY LOCATIONS OF PERTINENT SITE IMPROVEMENTS INSTALLED UNDER OTHER SECTIONS. IF ANY PART OF THIS PLAN CANNOT BE FOLLOWED DUE TO SITE CONDITIONS CONTACT LANDSCAPE ARCHITECT FOR INSTRUCTIONS PRIOR TO COMMENCING WORK
- PLANTING
- QUANTITIES SHOWN IN THE PLANT LIST ARE PROVIDED FOR THE CONVENIENCE OF THE INSTALLER & FOR OWNER INFORMATION. PROVIDE THE QUANTITY OF PLANTS SHOWN GRAPHICALLY ON THE PLANS. IN THE CASE OF A DISCREPANCY THE PLANS SHALL OVERRULE THE LEGENDS EXCEPT PLANTS SPECIFICALLY NOTED AS "NOT SHOWN ON PLAN". VERIFY PLANT COUNTS AND SQUARE FOOTAGES
  - TREES SHALL BE PLANTED AT FINISHED GRADE AS THEY BORE TO THE NATURAL GRADE BEFORE TRANSPLANTING
  - TREES TO BE PLANTED A MINIMUM OF 4 FEET FROM FACE OF BUILDING, OR PAVEMENT, EXCEPT AS APPROVED BY LANDSCAPE ARCHITECT
  - PROVIDE MATCHING FORMS AND SIZES FOR PLANT MATERIALS WITHIN EACH SPECIES AND SIZE DESIGNATED ON THE DRAWINGS
  - PRUNE NEWLY PLANTED TREES ONLY AS DIRECTED BY LANDSCAPE ARCHITECT
  - ALIGN AND EQUALLY SPACE IN ALL DIRECTIONS TREES AND SHRUBS SO DESIGNATED PER THESE NOTES AND DRAWINGS
  - FINISH GRADES OF PLANTER AREAS SHALL BE 2 INCHES BELOW ADJACENT PAVING OR TOP OF WALL UNLESS OTHERWISE NOTED
  - REMOVE ENTIRE WIRE CAGE FROM ROOTBALL, CUT AND REMOVE BURLAP FROM TOP 10 OF BALL
  - INDICATES AREA TO BE PLANTED WITH GROUNDCOVER, PERENNIALS, MULCH, OR ANNUALS
  - OWNER IS RESPONSIBLE FOR ALL PLANT WATERING



TALLGRASS LANDSCAPE ARCHITECTURE  
2318 B LINDSEY ROAD  
SOUTH DAKOTA 57073  
T: 605.462.2214  
F: 605.462.2214  
WWW.TALLGRASSLANDSCAPEARCHITECTURE.COM

OWNER:  
SUNNY & PROPERTIES LLC  
2917 Park St  
Sioux Falls, SD 57102  
605.343.3854



Use South Dakota One Call to locate underground utilities before you dig. Excavation planning to dig, drill or trench should make the required calls request to South Dakota One Call two working days before the planned work.

Make your locate request by simply calling 811 (person) and (605) 791-6744 outside of South Dakota. Locate requests are accepted 24/7. The One Call service is free to customers. www.onecall.org

THESE DRAWINGS ARE CONCEPT DRAWINGS BASED UPON AERIAL PHOTOGRAPHY AND SIMPLE SITE OBSERVATION AND ARE MEANT TO RELAY THE CONCEPTUAL SITE CONFIGURATION OF THE PLAY AREAS. THEY ARE NOT MEANT TO REPRESENT FINAL LAYOUT AND GRADING INFORMATION, BUT BATHES SITE PERFORMANCE INFORMATION AND MINIMUM OR MAXIMUM GRADING, LAYOUT, DIMENSIONAL AND AREA REQUIREMENTS. FINAL LAYOUT AND GRADING DECISIONS SHALL BE MADE ON SITE THROUGH JOINT CONSENSUS BETWEEN THE CONTRACTOR, LANDSCAPE ARCHITECT AND OWNER.

REVISIONS:

DATE:	BY:

RELEASE DATE: 2015-12-11  
PROJECT CONTACT: MATT  
PROJECT NUMBER: 2015-0222

PRELIMINARY DOCUMENTS

THE GARFIELD  
RAPID CITY, SD

PLANTING PLAN

SHEET: L-4  
OF 4

RECEIVED

DEC 11 2015