

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER NO. 3F
38TH STREET SANITARY SEWER EXTENSION
SSW01-1080
SEPTEMBER 27, 2001
ORIGINAL CONTRACT AMOUNT: \$114,081.00
CONTRACTOR: MAINLINE CONTRACTING, INC.

LINE ITEM	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	INSTALLED QUANTITY	INSTALLED PRICE	INCREASE/ (DECREASE)
1	MOBILIZATION	LS	1.00	\$2,800.00	\$2,800.00	1	\$2,800.00	\$0.00
2	8" SEWER MAIN (8'-12' BURY)	LF	388.00	\$17.00	\$6,596.00	388	\$6,596.00	\$0.00
3	8" SEWER MAIN (12'-14' BURY)	LF	125.00	\$22.00	\$2,750.00	125	\$2,750.00	\$0.00
4	4" SEWER SERVICE	LF	295.00	\$20.00	\$5,900.00	295	\$5,900.00	\$0.00
5	STANDARD MANHOLE 48" DIA.	EA	2.00	\$1,400.00	\$2,800.00	2	\$2,800.00	\$0.00
6	CONNECT TO EXISTING MANHOLE	EA	1.00	\$1,100.00	\$1,100.00	1	\$1,100.00	\$0.00
7	DISCONNECT & PLUG SEWER MAIN	EA	2.00	\$500.00	\$1,000.00	2	\$1,000.00	\$0.00
8	RESHAPE MANHOLE INVERT	EA	1.00	\$500.00	\$500.00	1	\$500.00	\$0.00
9	RECONNECT SEWER SERVICE	EA	11.00	\$750.00	\$8,250.00	11	\$8,250.00	\$0.00
10	8" C900 PVC WATER MAIN	LF	543.00	\$18.00	\$9,774.00	543	\$9,774.00	\$0.00
11	6" C900 PVC WATER MAIN	LF	9.00	\$30.00	\$270.00	9	\$270.00	\$0.00
12	1" COPPER SERVICE	LF	237.00	\$21.00	\$4,977.00	237	\$4,977.00	\$0.00
13	6" TO 8" REDUCER	EA	2.00	\$225.00	\$450.00	2	\$450.00	\$0.00
14	8" 90 DEGREE BEND	EA	2.00	\$250.00	\$500.00	2	\$500.00	\$0.00
15	6" X 6" X 6" TAPPING TEE	EA	1.00	\$1,000.00	\$1,000.00	1	\$1,000.00	\$0.00
16	8" X 8" X 6" TEE	EA	2.00	\$275.00	\$550.00	2	\$550.00	\$0.00
17	8" GATE VALVE W/BOX	EA	1.00	\$650.00	\$650.00	1	\$650.00	\$0.00
18	FIRE HYDRANT, AUXILLARY VALVE & LEAD	EA	2.00	\$2,200.00	\$4,400.00	2	\$4,400.00	\$0.00
19	1" CURB STOP W/ BOX	EA	9.00	\$140.00	\$1,260.00	9	\$1,260.00	\$0.00
20	1" TO 3/4" REDUCER	EA	11.00	\$32.00	\$352.00	11	\$352.00	\$0.00
21	CONNECT WATER MAIN @ CLIFTON	EA	1.00	\$1,200.00	\$1,200.00	1	\$1,200.00	\$0.00
22	CONNECT WATER MAIN @ STA 5+30	EA	1.00	\$1,200.00	\$1,200.00	1	\$1,200.00	\$0.00
23	1" TAPPING SADDLE & CORPORATION STOP	EA	11.00	\$570.00	\$6,270.00	11	\$6,270.00	\$0.00
24	MECHANICAL JOINT PLUG	EA	1.00	\$180.00	\$180.00	1	\$180.00	\$0.00
25	RECONNECT WATER SERVICE LINE	EA	11.00	\$500.00	\$5,500.00	11	\$5,500.00	\$0.00
26	PLUG EXISTING 6" CAST IRON WATER MAIN	EA	2.00	\$180.00	\$360.00	2	\$360.00	\$0.00
27	AGGREGATE BASE COURSE	TON	250.00	\$15.00	\$3,750.00	136.96	\$2,054.40	(\$1,695.60)
28	MILL & REMOVE ASPHALT PAVEMENT FULL	SY	2,020.00	\$5.00	\$10,100.00	2070	\$10,350.00	\$250.00
29	REMOVE CONCRETE APPROACH PAVEMENT	SY	65.80	\$7.00	\$460.60	65.8	\$460.60	\$0.00
30	REMOVE APPROACH PAVEMENT	SF	99.00	\$2.50	\$247.50	165	\$412.50	\$165.00
31	REMOVE & REPLACE ROCK WALL	LS	1.00	\$500.00	\$500.00	1	\$500.00	\$0.00
32	REMOVE AND RELOCATE STOP SIGN	EA	1.00	\$55.00	\$55.00	1	\$55.00	\$0.00
33	REMOVE & REPLACE CURB AND GUTTER	FT	24.00	\$20.00	\$480.00	90.5	\$1,810.00	\$1,330.00
34	CONCRETE APPROACH PAVEMENT 6"	SY	37.00	\$55.00	\$2,035.00	32.8	\$1,804.00	(\$231.00)
35	GRAVEL SURFACING	TON	22.00	\$16.00	\$352.00	15.42	\$246.72	(\$105.28)
36	ASPHALT CONCRETE CLASS G, TYPE 2, 2"	TON	295.00	\$39.50	\$11,652.50	216.58	\$8,554.91	(\$3,097.59)
37	ASPHALT CONCRETE, CLASS G, TYPE 1, 3"	TON	445.00	\$36.00	\$16,020.00	345.4	\$12,434.40	(\$3,585.60)

38	SEED, FERTILIZER	SY	220.00	\$1.50	\$330.00	440	\$660.00	\$330.00
39	INCIDENTAL	LS	1.00	\$2,500.00	\$2,500.00	1	\$2,500.00	\$0.00
40	TRAFFIC CONTROL	LS	1.00	\$2,600.00	\$2,600.00	1	\$2,600.00	\$0.00
41	TYPE I BEDDING	TON	437.16	\$14.00	\$6,120.24	450.42	\$6,305.88	\$185.64
42	EXTRA DEPTH MANHOLE	VFT	7.30	\$250.00	\$1,825.00	7.3	\$1,825.00	\$0.00
43	4" CONCRETE PAVEMENT	SF	0.00	\$4.80	\$0.00	424	\$2,035.20	\$2,035.20
TOTAL					\$129,616.84		\$125,197.61	(\$4,419.23)

C.C.O. HISTORY INCREASE/(DECREASE)		PRIOR ADJUSTED CONTRACT PRICE :	\$129,616.84
CCO #1	\$4,761.64 NET INCREASE/(DECREASE):		(\$4,419.23)
CCO #2	\$10,774.20		
CCO #3	-\$4,419.23 ADJUSTED CONTRACT PRICE:		\$125,197.61
PRIOR TOTAL =	\$15,535.84 CHANGE TO DATE:		\$11,116.61

CONTRACTOR: _____	DATE: _____
ENGINEER: _____	DATE: _____
MAYOR: _____	DATE: _____
FINANCE: _____	DATE: _____
CONTRACT TIME CHANGE +/-: 0	NEW CONTRACT TIME: _____ Days

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER NO. 3F
38TH STREET SANITARY SEWER EXTENSION
SSW01-1080
SEPTEMBER 27, 2001
ORIGINAL CONTRACT AMOUNT: \$114,081.00
CONTRACTOR: MAINLINE CONTRACTING, INC.

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
27	AGGREGATE BASE COURSE	(DECREASE 113.04 TONS) WAS NOT NEEDED FOR BASE COURSE BENEATH THE ASPHALT MILLINGS.
28	MILL & REMOVE ASPHALT PAVEMENT FULL	(INCREASE 50.0 SY) NORMAL VARIATION
30	REMOVE APPROACH PAVEMENT	(INCREASE 156.0 SF) INCREASE DUE TO PLAN ERROR IN ESTIMATING THE QUANTITY.
33	REMOVE & REPLACE CURB AND GUTTER	(INCREASE 66.5 FT) INREASE DUE TO ADDITIONAL CURB NEEDED TO BE REMOVED IN ORDER TO INSTALL THE WATER MAIN.
34	CONCRETE APPROACH PAVEMENT 6"	(DECREASE 4.2 SY) NORMAL VARIATION
35	GRAVEL SURFACING	(DECREASE 6.58 TON) NORMAL VARIATION
36	ASPHALT CONCRETE CLASS G, TYPE 2, 2"	(DECREASE 78.42) NORMAL VARIATION
37	ASPHALT CONCRETE, CLASS G, TYPE 1, 3"	(DEREASE 100.0 TON) NORMAL VARIATION
38	SEED, FERTILIZER	(INCREASE 220.0 SY) DOUBLE AREA TO INCREASED WORK BACK OF CURB
41	TYPE I BEDDING	(INCREASE 13.26 TON) ORIGINALLY LEFT OFF OF BID ITEMS
43	4" CONCRETE PAVEMENT	(INCREASE 424.0 SF) SIDEWALK REPLACEMENT - NO ORIGINAL BID ITEM

PREPARED BY: _____

DATE: _____