

**CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1  
WHITEHEAD BALLFIELDS IMPROVEMENTS RESTROOM AND PICNIC SHELTER**

**PR04-1332**

**MAY 26, 2004**

**ORIGINAL CONTRACT AMOUNT: \$134,021.61**

**CONTRACTOR: TRU-FORM CONSTRUCTION INC.**

<b>LINE ITEM</b>	<b>DESCRIPTION</b>	<b>UNIT</b>	<b>CURRENT CONTRACT QUANTITY</b>	<b>UNIT PRICE</b>	<b>EXTENDED PRICE</b>	<b>ADJUSTED QUANTITY</b>	<b>ADJUSTED PRICE</b>	<b>NET CHANGE</b>
1	MOBILIZATION	LS	1.00	\$2,000.00	\$2,000.00		\$0.00	
2	RESTROOM AND PICNIC SHELTER	LS	1.00	\$80,000.00	\$80,000.00		\$0.00	
3	4" PVC SEWER SERVICE LINE	LF	217.00	\$13.81	\$2,996.77		\$0.00	
4	6" PVC SEWER SERVICE LINE	LF	633.00	\$15.67	\$9,919.11		\$0.00	
5	4" PVC CLEANOUT	EA	3.00	\$34.50	\$103.50		\$0.00	
6	6" PVC CLEANOUT	EA	7.00	\$34.50	\$241.50		\$0.00	
7	SEWER SERVICE CONNECTION	EA	1.00	\$57.50	\$57.50		\$0.00	
8	SEWER SERVICE CONCRETE ENCASEMENT	EA	1.00	\$690.00	\$690.00		\$0.00	
9	CONNECTION TO EXISTING SEWER SERVICE	EA	2.00	\$57.50	\$115.00		\$0.00	
10	2" COPPER WATER SERVICE	LF	100.00	\$19.68	\$1,968.00		\$0.00	
11	2" TAPPING SADDLE AND CORP STOP	EA	1.00	\$460.00	\$460.00		\$0.00	
12	2" CURB STOP AND BOX	EA	1.00	\$288.00	\$288.00		\$0.00	
13	1" BLOW OUT ASSEMBLY	EA	1.00	\$403.00	\$403.00		\$0.00	
14	12" X 6" TAPPING SLEEVE, VALVE & BOX	EA	1.00	\$1,870.00	\$1,870.00		\$0.00	
15	6" 45 DEGREE BEND W/ RESTRAINING GLANDS	EA	2.00	\$172.50	\$345.00		\$0.00	
16	FIRE HYDRANT AND LEAD	EA	1.00	\$2,860.00	\$2,860.00		\$0.00	
17	TYPE 1 BEDDING MATERIAL	TON	140.00	\$12.65	\$1,771.00		\$0.00	
18	REMOVE MANHOLE	EA	1.00	\$345.00	\$345.00		\$0.00	

19	REMOVE TREE, 12"-24"	EA	1.00	\$57.50	\$57.50		\$0.00	
20	CONCRETE SIDEWALK, 4"	SF	3,170.00	\$3.75	\$11,887.50		\$0.00	
21	SEEDING, FERTILIZING & MULCHING	SY	3,700.00	\$1.02	\$3,774.00		\$0.00	
	<b>ADD-ON ALTERNATES</b>							
A1	FURNISH AND INSTALL BURNISHED BLOCK, OUTSIDE WALLS	LS	1.00	\$8,300.00	\$8,300.00		\$0.00	
A2	FURNISH AND INSTALL PICNIC TABLES	LS	1.00	\$3,569.23	\$3,569.23		\$0.00	
	<b>CHANGE ORDER #1</b>							
22	4" PVC PERFORATED DRAIN PIPE WITH BALLAST ROCK	LS		\$1,572.77	\$0.00	1	\$1,572.77	\$1,572.77
<b>TOTAL</b>					<b>\$134,021.61</b>		<b>\$1,572.77</b>	<b>\$1,572.77</b>

C.C.O. HISTORY INCREASE/(DECREASE)		PRIOR ADJUSTED CONTRACT PRICE :		\$134,021.61
CCO #1	\$1,572.77	NET INCREASE/(DECREASE):		\$1,572.77
CCO #2		ADJUSTED CONTRACT PRICE:		\$135,594.38
CCO #3		CHANGE TO DATE:		\$1,572.77

CONTRACTOR: _____	DATE: _____
TRU-FORM CONSTRUCTION, INC. - 787-5187	
PROJECT MANAGER: _____	DATE: _____
KEITH JOHNSON	
MAYOR: _____	DATE: _____
JIM SHAW	
FINANCE: _____	DATE: _____
JIM PRESTON	
CONTRACT TIME CHANGE +/-: 0	NEW CONTRACT TIME: Days

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1  
WHITEHEAD BALLFIELDS IMPROVEMENTS RESTROOM AND PICNIC SHELTER  
PR04-1332  
MAY 26, 2004  
ORIGINAL CONTRACT AMOUNT: \$134,021.61  
CONTRACTOR: TRU-FORM CONSTRUCTION INC.

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
22	4" PVC PERFORATED DRAIN PIPE WITH BALLAST ROCK	GROUND WATER ELEVATION WAS ABOVE BOTTOM OF FOOTINGS AND NEEDED TO BE LOWERED

PREPARED BY: KEITH JOHNSON

DATE: MAY 26, 2004