




CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1F
 HIGHWAY 16 FIRE STATION DETENTION CELL
 RAPID CITY PROJECT NO. DR03-1268 / CIP NO. 50440
 JULY 31, 2009
 ORIGINAL CONTRACT AMOUNT: \$173,533.30
 CONTRACTOR: SITE WORK SPECIALISTS, INC.

LINE ITEM	DESCRIPTION	UNIT	CURRENT CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	ADJUSTED QUANTITY	ADJUSTED PRICE	NET CHANGE
1	MOBILIZATION	LS	1.00	\$3,000.00	\$3,000.00	1.00	\$3,000.00	\$0.00
2	CONSTRUCTION STAKING	LS	1.00	\$5,000.00	\$5,000.00	1.00	\$5,000.00	\$0.00
3	CLEARING & GRUBBING 6"+ TREE	EA	21.00	\$200.00	\$4,200.00	21.00	\$4,200.00	\$0.00
4	CLEARING	LS	1.00	\$2,000.00	\$2,000.00	1.00	\$2,000.00	\$0.00
5	UNCLASSIFIED EXCAVATION	CY	6,600.00	\$1.30	\$8,580.00	8,611.00	\$11,194.30	\$2,614.30
6	IMPORTED BORROW	CY	3,250.00	\$5.00	\$16,250.00	3,250.00	\$16,250.00	\$0.00
7	PLACE TOPSOIL	CY	1,350.00	\$2.15	\$2,902.50	1,350.00	\$2,902.50	\$0.00
8	SALVAGE TOPSOIL	CY	1,350.00	\$1.20	\$1,620.00	1,350.00	\$1,620.00	\$0.00
9	12" RCP, CLASS II	LF	40.00	\$24.00	\$960.00	40.00	\$960.00	\$0.00
10	18" RCP, CLASS V	LF	14.00	\$37.00	\$518.00	18.00	\$666.00	\$148.00
11	48" RCP, CLASS V	LF	130.00	\$195.00	\$25,350.00	130.00	\$25,350.00	\$0.00
12	12" RCP FLARED END	EA	2.00	\$550.00	\$1,100.00	2.00	\$1,100.00	\$0.00
13	48" RCP FLARED END	EA	1.00	\$1,650.00	\$1,650.00	1.00	\$1,650.00	\$0.00
14	OUTLET STRUCTURE A	LS	1.00	\$19,500.00	\$19,500.00	1.00	\$19,500.00	\$0.00
15	OUTLET STRUCTURE B	LS	1.00	\$14,000.00	\$14,000.00	1.00	\$14,000.00	\$0.00
16	OUTLET STRUCTURE C	LS	1.00	\$14,000.00	\$14,000.00	1.00	\$14,000.00	\$0.00
17	CLASS III RIPRAP	T	290.00	\$50.00	\$14,500.00	290.00	\$14,500.00	\$0.00
18	SURFACE ROUGHENING	AC	1.60	\$2,200.00	\$3,520.00	1.60	\$3,520.00	\$0.00
19	VEHICLE TRACKING CONTROL	EA	1.00	\$1,000.00	\$1,000.00	1.00	\$1,000.00	\$0.00
20	INLET PROTECTION	EA	2.00	\$50.00	\$100.00	3.00	\$150.00	\$50.00
21	CONCRETE WASHOUT AREA	1.00	1.00	\$350.00	\$350.00	0.00	\$0.00	(\$350.00)
22	SILT FENCE	LF	50.00	\$4.00	\$200.00	47.00	\$188.00	(\$12.00)
23	WATTLE, 9"	LF	60.00	\$3.00	\$180.00	140.00	\$420.00	\$240.00
24	EROSION CONTROL BLANKET	SY	7,900.00	\$3.00	\$23,700.00	7,900.00	\$23,700.00	\$0.00
25	SEEDING	SY	9,615.00	\$0.25	\$2,403.75	9,615.00	\$2,403.75	\$0.00
26	FERTILIZING	SY	9,615.00	\$0.17	\$1,634.55	9,615.00	\$1,634.55	\$0.00
27	MULCHING	SY	1,715.00	\$0.30	\$514.50	1,715.00	\$514.50	\$0.00
28	INCIDENTAL WORK	LS	1.00	\$4,800.00	\$4,800.00	1.00	\$4,800.00	\$0.00
29	ROCK EXCAVATION	LS	0.00	\$4,122.15	\$0.00	1.00	\$4,122.15	\$4,122.15
30	LIQUIDATED DAMAGES	DAY	0.00	(\$450.00)	\$0.00	21.00	(\$9,450.00)	(\$9,450.00)
TOTAL					\$173,533.30		\$170,895.75	(\$2,637.55)

C.C.O. HISTORY INCREASE/(DECREASE)		PRIOR ADJUSTED CONTRACT PRICE :	\$173,533.30
CCOF #1	(\$2,637.55)	NET INCREASE/(DECREASE):	(\$2,637.55)
	\$0.00	ADJUSTED CONTRACT PRICE:	\$170,895.75
	\$0.00	CHANGE TO DATE:	(\$2,637.55)

	DATE	11/4/10
CONTRACTOR: Site Work Specialists, PO Box 7504, RC, SD 57709-7504 355-0933	DATE	4/21/10
	DATE	
PROJECT MANAGER: Klare Schroeder, P.E.	DATE	
	DATE	5-4-10
CITY ENGINEER: DALE TECH	DATE	
MAYOR: ALAN HANKS	DATE	
FINANCE: JAMES PRESTON Pauline Sumption	DATE	
CONTRACT TIME CHANGE +/-: +10 Days	NEW CONTRACT TIME: 6/30/09	

City Staff recommends approval of this Change Order #1F to Site Work Specialists, Inc. for an decrease of \$2,637.55 based on unit pricing with the following appropriation:

Initial Funding				\$173,533.30	\$173,533.30
Fund Type				Storm Sewer	
Department				8911	
Line Item				4371	
Fund				0505	
CCO #1F				(\$2,637.55)	(\$2,637.55)
Adjusted Funding				\$170,895.75	\$170,895.75

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1F
HIGHWAY 16 FIRE STATION DETENTION CELL
RAPID CITY PROJECT NO. DR03-1268 / CIP NO. 50440
JULY 31, 2009
ORIGINAL CONTRACT AMOUNT: \$173,533.30
CONTRACTOR: SITE WORK SPECIALISTS, INC.

ITEM	DESCRIPTION	REASON FOR CHANGE
5	UNCLASSIFIED EXCAVATION	Design error resulted in construction of facility lower than intended; therefore more excavation.
10	18" RCP, CLASS V	Plan error - diagonal distance between inlet structures required greater length of pipe than shown.
20	INLET PROTECTION	Additional inlet found which required protection.
21	CONCRETE WASHOUT AREA	None used.
22	SILT FENCE	Actual quantity used to construct project in accordance with plans & specs.
23	WATTLE, 9"	Additional waddles used to minimize erosion on hillside areas.
29	ROCK EXCAVATION	Bedrock found which had to be removed to place outlet pipe properly.
30	LIQUIDATED DAMAGES	Actual days beyond adjusted completion date used to complete project.

PREPARED BY: Klare Schroeder

DATE: July 31, 2009

FUNDING TYPE		Storm Sewer	
COST CENTER		8911	
LINE ITEM		4371	
FUND		0505	
ITEM NO.	DESCRIPTION OF ITEM	AMOUNT	PERCENT
1	MOBILIZATION	0.00	100%
2	CONSTRUCTION STAKING	0.00	100%
3	CLEARING & GRUBBING 6"+ TREE	0.00	100%
4	CLEARING	0.00	100%
5	UNCLASSIFIED EXCAVATION	2,614.30	100%
6	IMPORTED BORROW	0.00	100%
7	PLACE TOPSOIL	0.00	100%
8	SALVAGE TOPSOIL	0.00	100%
9	12" RCP, CLASS II	0.00	100%
10	18" RCP, CLASS V	148.00	100%
11	48" RCP, CLASS V	0.00	100%
12	12" RCP FLARED END	0.00	100%
13	48" RCP FLARED END	0.00	100%
14	OUTLET STRUCTURE A	0.00	100%
15	OUTLET STRUCTURE B	0.00	100%
16	OUTLET STRUCTURE C	0.00	100%
17	CLASS III RIPRAP	0.00	100%
18	SURFACE ROUGHENING	0.00	100%
19	VEHICLE TRACKING CONTROL	0.00	100%
20	INLET PROTECTION	50.00	100%
21	CONCRETE WASHOUT AREA	-350.00	100%
22	SILT FENCE	-12.00	100%
23	WATTLE, 9"	240.00	100%
24	EROSION CONTROL BLANKET	0.00	100%
25	SEEDING	0.00	100%
26	FERTILIZING	0.00	100%
27	MULCHING	0.00	100%
28	INCIDENTAL WORK	0.00	100%
29	ROCK EXCAVATION	4,122.15	100%
30	LIQUIDATED DAMAGES	-9,450.00	100%
		(\$2,637.55)	

(\$2,637.55)