

**CITY OF RAPID CITY  
CONSTRUCTION CHANGE ORDER**

PROJECT NAME: ORIGINAL TOWNSITE SANITARY SEWER RECONSTRUCTION

PROJECT NO: SS00-941

CONTRACTOR: RAPID CONSTRUCTION CO

ORIGINAL CONTRACT AMOUNT: \$242,300.10



CHANGE ORDER NO.: 1

DATE: 18-Dec-00

LINE ITEM	SEC NO	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	INSTALLED QUANTITY	INSTALLED PRICE	INCREASE/ (DECREASE)
1	A001	MOBILIZATION	LS	1	\$9,000.00	\$9,000.00		\$0.00	
2	C0014	8" PVC SEWER MAIN ( 6'- 8')	FT	487	\$42.80	\$20,843.60		\$0.00	
3	C0015	8" PVC SEWER MAIN ( 8'-10')	FT	965	\$42.80	\$41,302.00		\$0.00	
4	C0077	4" PVC SERVICE LINE	FT	161	\$35.00	\$5,635.00		\$0.00	
5	C0078	6" PVC SERVICE LINE	FT	54	\$35.00	\$1,890.00		\$0.00	
6	C0088	EXTRA MANHOLE DEPTH, 48" DIA.	V FT	15	\$140.00	\$2,100.00		\$0.00	
7	C0091	STANDARD MANHOLE, 48" DIA.	EA	5	\$1,450.00	\$7,250.00		\$0.00	
8	C0103	REMOVE MANHOLE	EA	8	\$500.00	\$4,000.00		\$0.00	
9	C0106	RECONNECT SEWER SERVICE	EA	27	\$320.00	\$8,640.00		\$0.00	
10	C	RECONNECT SEWER MAIN	EA	3	\$555.00	\$1,665.00		\$0.00	
11	E00010	EXPLORATORY EXCAVATION	HR	6	\$130.00	\$780.00		\$0.00	
12	E00031	TYPE I BEDDING MATERIAL	T	200	\$19.00	\$3,800.00		\$0.00	
13	E00033	TYPE II FOUNDATION MATERIAL	T	70	\$18.50	\$1,295.00		\$0.00	
14	G00010	EXCAVATION, UNCLASSIFIED	CY	687	\$8.00	\$5,496.00		\$0.00	
15	G00016	EXCAVATION, UNCLASSIFIED-DIGOUTS W/SUGAR ROCK	CY	20	\$30.00	\$600.00		\$0.00	
16	G00019	SUGAR ROCK, 3" TO 6" NOMINAL	T	40	\$13.50	\$540.00		\$0.00	
17	G00022	AASHTO T-180, SOIL TEST MODIFIED PROCTOR TEST	EA	5	\$143.00	\$715.00		\$0.00	
18	H00011	SAWING, ASPHALT PAVEMENT	FT	1687	\$1.50	\$2,530.50		\$0.00	
19	H00012	SAWING, CONCRETE PAVEMENT	FT	305	\$4.50	\$1,372.50		\$0.00	
20	H00031	REMOVE ASPHALT CONCRETE PAVEMENT	SY	2176	\$5.00	\$10,880.00		\$0.00	
21	H00033	REMOVE CONCRETE APPROACH PAVEMENT	SY	101	\$5.00	\$505.00		\$0.00	
22	H00035	REMOVE CONCRETE CURB AND GUTTER	FT	28	\$4.00	\$112.00		\$0.00	
23	H00042	REMOVE CONCRETE PAVEMENT	SY	1215	\$6.00	\$7,290.00		\$0.00	
24	H00044	REMOVE CONCRETE SIDEWALK	SY	34	\$6.00	\$204.00		\$0.00	
25	I00011	AGGREGATE BASE COURSE	T	1250	\$15.00	\$18,750.00		\$0.00	
26	I00030	ASPHALT CONCRETE, CLASS G, TYPE 1	T	753	\$43.50	\$32,755.50		\$0.00	
27	I00031	ASPHALT CONCRETE, CLASS G, TYPE 2	T	252	\$52.50	\$13,230.00		\$0.00	
28	I00041	CONCRETE APPROACH PAVEMENT, REINFORCED, 6"	SY	55	\$41.00	\$2,255.00		\$0.00	
29	I00047	CONCRETE DRIVEWAY PAVEMENT, REINFORCED, 6"	SY	24	\$41.00	\$984.00		\$0.00	
30	I00049	DOWEL BAR ASSEMBLY	FT	37	\$9.00	\$333.00		\$0.00	
31	I00057	PCC PAVEMENT, 7" NONREINFORCED	SY	215	\$39.00	\$8,385.00		\$0.00	
32	I00067	CONCRETE "P6" GUTTER	FT	90	\$17.00	\$1,530.00		\$0.00	
33	I00081	CONCRETE DRAIN PAN (REINFORCED), 6"	SY	190	\$43.00	\$8,170.00		\$0.00	

34	I00093	CONCRETE SIDEWALK, 6", REINFORCED	S FT	286	\$4.50	\$1,287.00		\$0.00	
35	0	ABANDON WATER FLUSHING LINE	EA	2	\$2,000.00	\$4,000.00		\$0.00	
36	M00030	TRAFFIC CONTROL	LS	1	\$10,575.00	\$10,575.00		\$0.00	
37	N00010	INCIDENTAL WORK	LS	1	\$1,600.00	\$1,600.00		\$0.00	
	0	Change Order No.: #1		0	\$0.00	\$0.00		\$0.00	
38	I00014	SOIL SUPPORT FABRIC/GEOGRID	SY	0	\$3.00	\$0.00	1003	\$3,009.00	\$3,009.00
		<b>TOTAL</b>				\$242,300.10		\$3,009.00	\$3,009.00

C.C.O. HISTORY INCREASE/(DECREASE)	PRIOR ADJUSTED CONTRACT PRICE :	\$242,300.10
CCO #1	NET INCREASE/(DECREASE) this C.O.:	\$3,009.00
CCO #2		
CCO #3	ADJUSTED CONTRACT PRICE:	\$245,309.10
PRIOR TOTAL =	CHANGE TO DATE:	\$3,009.00
\$0.00		

CONTRACTOR:		DATE:	12/18/00
ENGINEER:		DATE:	12/18/00
MAYOR:	_____	DATE:	_____
FINANCE:	_____	DATE:	_____
CONTRACT TIME CHANGE +/-: 0	NEW CONTRACT TIME:	Days	

