

FOURFRONT DESIGN INC. 30" COLUMN WITH TRELLIS POLE BASE

NOTE: ALL STEEL & BOLTS TO BE HOT DIP GALVANIZED, UNLESS NOTED ,8x8 SMOOTH FINISHED COLUMN, DOUGLAS FIR, COPPER NAPTHEMATE PRESSURE TREATED, CONSIDER USING SELECT DECK PRODUCTS 1'-6"-X"x4" PLATE EACH SIDE, W/(3) %" THRU BOLTS, (TYP.), ATTACH WITH %6" FILLET WELD. 8½"x8½"x½" EMBED PLATE, W/(4) ½"ø x 18" DBA, PROVIDE NON-SHRINK GROUT BELOW, POWDER COAT BLACK FINISH MORTAR BED FOR CAP. -(CAST IN PLACE) REINFORCED PRECAST COLORED CONCRETE CAP: INTEGRAL COLOR (WHITE) TO BE SELECTED FROM #3 EPOXY COATED REBAR @ 12" CC, EACH WAY CENTERED MANUFACTURER'S FULL RANGE, (AS SPECIFIED) - SEE TOP OF CONCRETE (TOC)
ON GRADING PLANS FOR SPOT LOUVERED FIXTURE, SUPPLY CONDUIT WITH ELECTRICAL SUPPLY, PER LOCAL/NATIONAL CODE DRIP EDGE, \* "x", (TYP.) - STONE VENEER, (NATURAL COLORS) #4 REBAR @ 18" O.C. OR AS SHOWN, (TYP.) - REINFORCED CONCRETE COLUMN, (POURED IN PLACE) - ISOLATION JOINT & CAULK, (TYP.) 6" REINFORCED SIDEWALK #4 REBAR @ 16" O.C. --EACH WAY, (TYP.), EACH FACE 20"x20" CONCRETE PIER W/(8) #5 VERT. REBAR & #3 TIES @ 16" CC - 2'-8"x2'-8"x8"
CONCRETE FOOTING
W/(4) #5, EACH
WAY CENTERED UNDISTURBED OR COMPACTED SUBGRADE

> STABILIZED AGGREGATE PATH (SIMILAR) 3/4"=1"-0"

L1.02

1/2"=1'-0"

L1.02

ermit 1 Use Conditional

Submittal

Trinity Eco Prayer Park Trinity Lutheran Endowment Foundation 305 Saint Francis

Site Details & Notes L1.02