

**CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1
KNOLLWOOD DETENTION POND ELEMENT 310**

DR00-902

JULY 2, 2003

ORIGINAL CONTRACT AMOUNT: \$310,926.00

CONTRACTOR: RCS CONSTRUCTION, INC.

LINE ITEM	DESCRIPTION	UNIT	CURRENT CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	ADJUSTED QUANTITY	ADJUSTED PRICE	NET CHANGE
1	CLEARING & GRUBBING, TREES	EA	50.00	\$120.00	\$6,000.00		\$0.00	
2	CLEARING & GRUBBING	LS	1.00	\$6,000.00	\$6,000.00		\$0.00	
3	6" CORRUG. PERF PIPE w/ FILT. SOCK/ CHECK VALVE	LF	350.00	\$12.00	\$4,200.00		\$0.00	
4	CLEAN SAND (SELECT GRANULAR BACKFILL)	T	10.00	\$21.00	\$210.00		\$0.00	
5	MUCK EXCAVATION (TRENCH)	CY	20.00	\$15.00	\$300.00		\$0.00	
6	CONTROLLED LOW STRENGTH BACKFILL MATERIAL	CY	20.00	\$90.00	\$1,800.00		\$0.00	
7	TYPE II FOUNDATION MATERIAL	T	15.00	\$20.00	\$300.00		\$0.00	
8	EXCAVATION, UNCLASSIFIED (incl. disposal)	CY	6,300.00	\$8.00	\$50,400.00	11520	\$92,160.00	\$41,760.00
9	EMBANKMENT MATERIAL	CY	5,300.00	\$7.00	\$37,100.00	10992	\$76,944.00	\$39,844.00
10	TYPE III FOUNDATION MATERIAL	T	165.00	\$20.00	\$3,300.00	312.42	\$6,248.40	\$2,948.40
11	TOPSOIL, FURNISH & PLACE	CY	500.00	\$18.50	\$9,250.00		\$0.00	
12	TOPSOIL, STOCKPILE & REPLACE	CY	120.00	\$6.00	\$720.00		\$0.00	
13	AGGREGATE BASE COURSE	T	75.00	\$15.00	\$1,125.00		\$0.00	
14	ASPHALT, REMOVE AND DISPOSE	SY	50.00	\$6.00	\$300.00		\$0.00	
15	AC PATCHING CL.G, TYPE 1, 5"	SY	30.00	\$40.00	\$1,200.00		\$0.00	
16	48" RCP to RCPA TRANSITION, CLASS III	EA	2.00	\$2,200.00	\$4,400.00		\$0.00	
17	48" RCP ARCH, CLASS III	LF	304.00	\$138.00	\$41,952.00		\$0.00	
18	48" RCP, CLASS III	LF	250.00	\$108.00	\$27,000.00		\$0.00	
19	48" RCP, CLASS III, 7.5 DEG. BEND	EA	4.00	\$400.00	\$1,600.00		\$0.00	
20	48" RCPA , CLASS III, 15 DEG. BENDS	EA	1.00	\$1,900.00	\$1,900.00		\$0.00	
21	48" RCPA , CLASS III, 22.5 DEG. BENDS	EA	6.00	\$1,900.00	\$11,400.00		\$0.00	
22	48" RCP , CLASS III, 45 DEG. BENDS	EA	2.00	\$1,700.00	\$3,400.00		\$0.00	
23	MANHOLE ON 48" RCPA W/TYPE 2 COVER/ADJ. RINGS	EA	3.00	\$2,100.00	\$6,300.00		\$0.00	
24	OUTLET DRAIN, RC, CANAL GATE STRUCTURE	LS	1.00	\$1,000.00	\$1,000.00		\$0.00	
25	72" RISER TRASH RACK	EA	1.00	\$5,100.00	\$5,100.00		\$0.00	
26	72" PRECAST RCP RISER CLASS III, AND BASE	LF	10.00	\$330.00	\$3,300.00		\$0.00	
27	TYPE IV FOUNDATION MATERIAL	T	11.00	\$16.00	\$176.00		\$0.00	
28	PIPE BOLLARDS AND CHAIN	LS	1.00	\$800.00	\$800.00		\$0.00	
29	GRAVEL SURFACING	T	35.00	\$16.00	\$560.00		\$0.00	
30	18" RCP FLARED END SECTION & TRASH RACK	EA	1.00	\$900.00	\$900.00		\$0.00	
31	GROUTED RIP-RAP DROP STRUCTURE	SY	167.00	\$103.00	\$17,201.00		\$0.00	
32	REMOVE CONCRETE CURB & GUTTER	LF	35.00	\$5.00	\$175.00		\$0.00	
33	WATER MAIN LOWERING (8")	EA	1.00	\$2,300.00	\$2,300.00		\$0.00	
34	CLASS 3 RIPRAP W/BEDDING	CY	260.00	\$43.00	\$11,180.00		\$0.00	
35	FILTER FABRIC, NONWOVEN	SY	700.00	\$1.70	\$1,190.00		\$0.00	
36	EROSION CONTROL, HAY BALES	EA	20.00	\$20.00	\$400.00		\$0.00	
37	EROSION CONTROL, SILT FENCE	LF	1,230.00	\$3.00	\$3,690.00		\$0.00	

LINE ITEM	DESCRIPTION	UNIT	CURRENT CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	ADJUSTED QUANTITY	ADJUSTED PRICE	NET CHANGE
38	EROSION CONTROL, HI-VELOCITY EXCELSIOR BLANKET	SY	280.00	\$4.00	\$1,120.00		\$0.00	
39	EROSION CONTROL, EXCELSIOR BLANKET	SY	6,000.00	\$1.80	\$10,800.00		\$0.00	
40	EROSION CONTROL, COCONUT/STRAW BLANKET	SY	900.00	\$1.75	\$1,575.00		\$0.00	
41	SEEDING, FERTILIZING, MULCHING	SY	6,200.00	\$0.66	\$4,092.00		\$0.00	
42	MOBILIZATION	LS	1.00	\$15,000.00	\$15,000.00		\$0.00	
43	EXPLORATORY EXCAVATION (POTHOLE WATERMAIN)	HR	2.00	\$100.00	\$200.00		\$0.00	
44	REMOVE/REPLACE 4 INCH SIDEWALK	SF	350.00	\$5.00	\$1,750.00		\$0.00	
45	CONCRETE APPROACH PAVEMENT, REINF., 6"	SY	39.00	\$40.00	\$1,560.00		\$0.00	
46	REMOVE SIDEWALK, EXPOSED AGGREGATE	SF	210.00	\$1.00	\$210.00		\$0.00	
47	EXPOSED AGGREGATE SIDEWALK	SF	120.00	\$4.50	\$540.00		\$0.00	
48	INCIDENTAL COSTS	LS	1.00	\$4,000.00	\$4,000.00		\$0.00	
49	WATERWAY POLLUTION CONTROL	LS	1.00	\$1,500.00	\$1,500.00		\$0.00	
50	CONCRETE TEST SET	EA	3.00	\$150.00	\$450.00		\$0.00	
TOTAL						\$310,926.00	\$175,352.40	\$84,552.40

C.C.O. HISTORY INCREASE/(DECREASE)	PRIOR ADJUSTED CONTRACT PRICE :	\$0.00
CCO #1	NET INCREASE/(DECREASE):	\$84,552.40
CCO #2		
CCO #3	ADJUSTED CONTRACT PRICE:	\$84,552.40
PRIOR TOTAL =	CHANGE TO DATE:	\$84,552.40

CONTRACTOR: _____	DATE: _____
ENGINEER: _____ Rich Wells, PE/PLS	DATE: _____
MAYOR: _____ Jim Shaw	DATE: _____
FINANCE: _____ Jim Preston	DATE: _____
CONTRACT TIME CHANGE +/-: 0	NEW CONTRACT TIME: _____ Days

LINE ITEM	DESCRIPTION	UNIT	CURRENT CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	ADJUSTED QUANTITY	ADJUSTED PRICE	NET CHANGE
--------------	-------------	------	---------------------------------	---------------	-------------------	----------------------	-------------------	------------

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1

KNOLLWOOD DETENTION POND ELEMENT 310

DR00-902

JULY 2, 2003

ORIGINAL CONTRACT AMOUNT: \$310,926.00

CONTRACTOR: RCS CONSTRUCTION, INC.

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
8	EXCAVATION, UNCLASSIFIED (incl. disposal)	INCREASE DUE TO ADDITIONAL SOFT SOILS ENCOUNTERED DURING EXCAVATION
9	EMBANKMENT MATERIAL	EXTRA EMBANKMENT QUANTITIES WERE NECESSARY TO REPLACE EXTRA EXCAVATION
10	TYPE III FOUNDATION MATERIAL	EXTRA FOUNDATION ROCK WAS NECESSARY DUE TO ADDITIONAL SOFT SOILS

PREPARED BY: RICH WELLS

DATE: JULY 2,2003