

**CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1F
SHERIDAN LAKE ROAD / FAIRWAY HILLS DR STREET REPAIR
W03-1320
6/30/03**

ORIGINAL CONTRACT AMOUNT: \$28,794.50

CONTRACTOR: HEAVY CONSTRUCTORS, INC

LINE ITEM	DESCRIPTION	UNIT	CURRENT CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	ADJUSTED QUANTITY	ADJUSTED PRICE	NET CHANGE
1	MOBILIZATION	LS	1.00	\$1,500.00	\$1,500.00	1	\$1,500.00	\$0.00
2	SUGAR ROCK, 3" TO 6" NOMINAL	T	40.00	\$19.00	\$760.00	14.2	\$269.80	(\$490.20)
3	CONTROLLED LOW STRENGTH BACKFILL MATERIAL	CY	8.00	\$100.00	\$800.00	0	\$0.00	(\$800.00)
4	REMOVE & DISPOSE ASPHALT PAVEMENT	SY	100.00	\$5.00	\$500.00	28	\$140.00	(\$360.00)
5	REMOVE CONCRETE FILLET	SF	56.00	\$2.00	\$112.00	56	\$112.00	\$0.00
6	REMOVE CONCRETE CURB THROAT	LF	15.00	\$10.00	\$150.00	15	\$150.00	\$0.00
7	REMOVE CONCRETE SIDEWALK	SF	353.00	\$1.00	\$353.00	353	\$353.00	\$0.00
8	GRAVEL CUSHION	T	75.00	\$17.00	\$1,275.00	114	\$1,938.00	\$663.00
9	AC PATCHING, CLASS G, TYPE 1	T	3.00	\$100.00	\$300.00	8	\$800.00	\$500.00
10	CONCRETE APPROACH PAVEMENT, 8"	SY	75.00	\$50.00	\$3,750.00	70	\$3,500.00	(\$250.00)
11	DOWEL BAR ASSEMBLY	LF	84.00	\$4.00	\$336.00	120	\$480.00	\$144.00
12	PCC PAVEMENT JOINT SEAL	LF	374.00	\$2.00	\$748.00	575	\$1,150.00	\$402.00
13	CONCRETE TEST SET	EA	3.00	\$200.00	\$600.00	3	\$600.00	\$0.00
14	PCC PAVEMENT PANEL REPLACEMENT 8"	SY	140.00	\$55.00	\$7,700.00	201	\$11,055.00	\$3,355.00
15	FULL DEPTH PCC PAVEMENT REPAIR	SY	5.00	\$80.00	\$400.00	5	\$400.00	\$0.00
16	CONCRETE SIDEWALK, 4"	SF	423.00	\$3.50	\$1,480.50	395	\$1,382.50	(\$98.00)
17	CONCRETE FILLET & PAN (REINFORCED), 8"	SY	21.00	\$55.00	\$1,155.00	21	\$1,155.00	\$0.00
18	CONCRETE CURB THROAT	LF	15.00	\$25.00	\$375.00	15	\$375.00	\$0.00
19	INCIDENTAL	LS	1.00	\$1,500.00	\$1,500.00	1	\$1,500.00	\$0.00
20	TRAFFIC CONTROL	LS	1.00	\$5,000.00	\$5,000.00	1	\$5,000.00	\$0.00
	CHANGE ORDER #1F							
21	REMOVAL OF CONCRETE CURB & GUTTER	LF	0.00	\$3.00	\$0.00	48.0	\$144.00	\$144.00
22	B68 CONCRETE CURB & GUTTER	LF	0.00	\$14.00	\$0.00	48.0	\$672.00	\$672.00
	TOTAL				\$28,794.50		\$32,676.30	\$3,881.80

C.C.O. HISTORY INCREASE/(DECREASE)	PRIOR ADJUSTED CONTRACT PRICE :	\$0.00
	NET INCREASE/(DECREASE):	\$3,881.80
	ADJUSTED CONTRACT PRICE:	\$3,881.80
	CHANGE TO DATE:	\$3,881.80

CONTRACTOR: _____	DATE: _____
ENGINEER: _____ Curt Huus, P.E./L.S.	DATE: _____
MAYOR: _____	DATE: _____
FINANCE: _____	DATE: _____
CONTRACT TIME CHANGE +/-: 0	NEW CONTRACT TIME: _____ Days

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1F
SHERIDAN LAKE ROAD / FAIRWAY HILLS DR STREET REPAIR
W03-1320
6/30/03
ORIGINAL CONTRACT AMOUNT: \$28,794.50
CONTRACTOR: HEAVY CONSTRUCTORS, INC

LINE ITEM	DESCRIPTION	REASON FOR CHANGE
1 - 20	BID ITEMS	ADJUST BID QUANTITIES WITH ACTUAL INSTALLED QUANTITIES
9	AC PATCHING, CLASS G, TYPE 1	REMOVED AND REPLACED ADDITIONAL ASPHALT IN ORDER TO TIE INTO EXISTING ASPHALT BETTER
8	GRAVEL CUSHION	REMOVE AND REPLACE 3 ADDITIONAL PANELS DUE TO SEVERE WASHING OUT OF BASECOARSE UNDER PAVEMENT AND HEAVING DUE TO WATER MAIN BREAK THAT WAS NOT DISCOVERED UNTIL AFTER REMOVAL OF PLANS PANELS
11	DOWEL BAR ASSEMBLY	
12	PCC PAVEMENT JOINT SEAL	
14	PCC PAVEMENT PANEL REPLACEMENT, 8"	
21	REMOVAL OF CONCRETE CURB & GUTTER	ADDITIONAL PANEL REMOVAL CAUSED REMOVAL OF EXISTING CURB & GUTTER ADJACENT TO PANELS
22	B68 CONCRETE CURB & GUTTER	

PREPARED BY: CURT HUUS

DATE: JUNE 30, 2003