CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1F WELL #11 PUMP REPLACEMENT W04-1387

AUGUST 17, 2004

ORIGINAL CONTRACT AMOUNT: \$41,721.80 CONTRACTOR: WESTON ENGINEERING, INC.

LINE	DESCRIPTION	UNIT	CURRENT CONTRACT QUANTITY	UNIT PRICE	EXTENDED PRICE	ADJUSTED QUANTITY	ADJUSTED PRICE	NET CHANGE
1	MOBILIZATION	LS	1.00	\$1,500.00	\$1,500.00	2.00	\$3,000.00	\$1,500.00
2	REMOVE EXISTING WELL PUMP AND STOCKPILE	LS	1.00	\$600.00	\$600.00	1.00	\$600.00	\$0.00
3	FURNISH SUBMERSIBLE WELL PUMP AND MOTOR	LS	1.00	\$23,584.30	\$23,584.30	1.00	\$23,584.30	\$0.00
4	FURNISH 6" COLUMN PIPE	LF	200.00	\$22.40	\$4,480.00	211.38	\$4,734.91	\$254.91
5	FURNISH 4/0 (FLAT) SUBMERSIBLE PUMP CABLE	LF	500.00	\$10.85	\$5,425.00	530.00	\$5,750.50	\$325.50
6	FURNISH 6" CHECK VALVES	EA	2.00	\$425.00	\$850.00	2.00	\$850.00	\$0.00
7	FURNISH 1/4" AIRLINE	LF	530.00	\$0.25	\$132.50	530.00	\$132.50	\$0.00
8	FURNISH LEVEL TRANSDUCER SYSTEM	LS	1.00	\$3,150.00	\$3,150.00	1.00	\$3,150.00	\$0.00
9	INSTALL WELL PUMP AND ACCESSORIES	LS	1.00	\$750.00	\$750.00	1.00	\$750.00	\$0.00
10	WELL DISINFECTION	LS	1.00	\$500.00	\$500.00	1.00	\$500.00	\$0.00
11	INCIDENTAL WORK	LS	1.00	\$750.00	\$750.00	1.00	\$750.00	\$0.00
	TOTAL \$41,721.80 \$43,802.21 \$2,080.41							

C.C.O. HISTORY INCREASE/(DECI	REASE)		PRIOR ADJUSTE	PRIOR ADJUSTED CONTRACT PRICE :		
CCO #1F		\$2,080.41	NET INCREASE/(I	DECREASE):	\$2,080.41	
			ADJUSTED CONT	RACT PRICE:	\$43,802.21	
			CHANGE TO DAT	E:	\$2,080.41	
CONTRACTOR:				DATE: _		
ENGINEER:				DATE: _		
MAYOR:				DATE:		
FINANCE:				DATE:		
CONTRACT TIME CHANGE +/-: 0	NEW CONTRACT TIME	E: Davs				

CITY OF RAPID CITY CONSTRUCTION CHANGE ORDER #1F WELL #11 PUMP REPLACEMENT

W04-1387 AUGUST 17, 2004

ORIGINAL CONTRACT AMOUNT: \$41,721.80

CONTRACTOR: WESTON ENGINEERING, INC.

LINE		
ITEM	DESCRIPTION	REASON FOR CHANGE
1		THE EXISTING COLUMN PIPE WAS 8" INSTEAD OF 6". THE CONTRACTOR RETURNED TO UPTON TO RERIG TO HANDLE THE LARGER PIPE.
2	FURNISH 6" COLUMN PIPE	THE PUMP WAS ACTUALLY SET AT 523' INSTEAD OF 492' INCREASING THE BID QUANTITY.
3	FURNISH 4/0 (FLAT) SUBMERSIBLE PUMP CABLE	THE PUMP WAS ACTUALLY SET AT 523' INSTEAD OF 492' INCREASING THE BID QUANTITY.

PREPARED BY: STACEY TITUS DATE: AUGUST 18, 2004